

CODE COMPLIANCE CERTIFICATE

Section 95 Building Act 2004 [Form 7 – Building (forms) Regulations 2004]



Consent No(s): 240320

The Building			
Street address of building:	198-200 Maungakotukutuku Road, Paraparau	Building name:	N/A
Current, Lawfully established, use:	Detached Dwelling	Location of building within site/block number:	Centre of section remote from any boundaries
		Intended life of the building if 50 years or less:	-
Level/unit number:	-	Year first constructed:	1972
Legal description of land where building is located:	LOT 20 DP 33688		

The Owner			
Name of owner:	Peter Saunders and Usani Saunders	Street address /registered office:	198-200 Maungakotukutuku Road, Paraparaumu
Contact person:	As above	Phone numbers:	
Mailing address:	200 Maungakotukutuku Road Paraparaumu 5032	Landline:	-
		Mobile:	0212420309
		Daytime:	-
Email address:	pjsaunders@live.com	After hours:	-
Website:	N/A	Facsimile number:	-

First point of contact for communications with the Kapiti Coast District Council:	
Agent	craig@seajay.co.nz

Building Work	
Building Consent No(s):	240320
Issued by:	Kapiti Coast District Council

Code Compliance

The building consent authority named below is satisfied, on reasonable grounds, that:

- (a) the building work complies with the building consent

Michelle Salmon –
Building Inspections Team Leader
On behalf of **Kapiti Coast District Council**

Date: 11/03/2025

Seajay Consulting Engineers
PO Box 1713
Paraparaumu 5254

17 June 2024

Dear Building Consent Applicant / Building Owner

Approval of Building Consent – Detached Residential / Outbuilding: 240320

Location: 198-200 Maungakotukutuku Road, Parapara
Legal Description: LOT 20 DP 33688
Description: The project comprises construction of a new set of internal stairs in the existing two storey house.

I am pleased to inform you that the above building consent application has been approved. The building consent documents have been issued and are enclosed.

The building consent attached to this letter is consent under the Building Act 2004 to undertake building work in accordance with the plans and specifications that accompanied your application. Under section 49 of that Act, Council is satisfied that the provisions of the building code would be met if the proposed building work were completed in accordance with those plans and specifications. This consent does not affect any duty or responsibility under any other Act or permit any breach of any other Act.

This building consent does not give or imply any rights to transgress beyond your legal boundaries. Any work that is required beyond your legal boundaries can only be undertaken with the permission of the affected owner/s.

Before starting any work please read ALL the building consent documents carefully and in full so that you, as the owner, understand the conditions under which the consent has been issued.

Owner responsibilities

The owner is responsible for ensuring:

- building work starts within 12 months of the approval of the building consent and that work progresses at a reasonable pace.

- written notice of every licensed building practitioner undertaking restricted building work is provided to Council before that work commences, and any changes are advised in writing
- the approved building consent documents are kept on site during construction and available for the District inspector at inspections
- all required inspections are completed and that a Code Compliance Certificate is obtained once the work has been completed. The list of supporting documentation required before issue of the Code Compliance Certificate and information on filling out the application form for code compliance certificate is attached. Failure to obtain a final inspection and a code compliance certificate may affect your insurance cover and could affect future re-sale of your property.
- a Corridor Access Request is made and a Works Access permit is obtained before undertaking work in the legal road/road reserve, including installing a vehicle access crossing from the public road into your property. The process to be followed and the forms can be found on the Council website under Council Services/Roads or Council Services/Frequently asked questions/Access & Transport.
- before any excavations are undertaken a "Before U Dig" inquiry is made to check for locations of any underground services.
- no work with noisy equipment is to be carried out before 7.30 a.m. or after 6 p.m. Monday to Saturday. During the week there may be workers on site from 6.30 a.m. quietly preparing for work. Work with noisy equipment is not permitted on Sundays and public holidays.
- all loose materials that are capable of being carried by the wind are either secured or removed from the site. All activities must be carried out in a manner that keeps to a minimum the dust nuisance to adjacent properties.
- no damage occurs to public property, for example footpaths, water meters or retaining structures. Should damage occur you will be required to pay for any repairs.
- obtaining an amendment to the building consent for any changes to the approved building consent, prior to that work being undertaken.
- meeting the requirements of any easements, consent notices, covenants, and like listings registered on the title.
- the development contributions invoiced, if any, must be paid before a code compliance certificate can be issued.
- all maintenance recommended by the manufacturers is carried out at the required intervals.

General requirements

Note: Your attention is drawn to the notes contained in the 'Addendum to the Consent' and guidance documents referred to.

The following information is relevant to this building consent:

1. The Building Inspector is to be given 24 hours' notice before carrying out the inspections on the attached list. To arrange for inspections by the District Inspector, please contact the building inspectorate on 04 296 4700 between the hours of 8.00am and 4.30pm.
2. You are responsible for the safety of visitors to the work site including those undertaking building inspections. You must provide safe access to parts of the construction necessary for inspection. Ladder access must be securely founded and tied. Scaffold access and roof edge protection is generally required.
3. If required inspections, including those by designers of specifically designed elements, are not undertaken you may experience difficulty in obtaining a Code Compliance Certificate for the project. We suggest that at the time of the first inspection you discuss the inspection requirements with the inspecting officer.
4. This building consent will lapse and be of no effect if the building work concerned has not been commenced within 12 calendar months after the date of issue, or within such further period as the territorial authority allows.
5. The contractor is to leave the site clear of all demolition materials and in a tidy state.
6. Easements, consent notices, covenants, and like listings registered on the title are the responsibility of the applicant.
7. Note and comply with endorsements on approved plans.

Please note that the design work and restricted building work must be supervised or carried out by a licensed building practitioner who is licensed to carry out or supervise that kind of building work.

You or your agent will need to provide their details to the Council in writing prior to commencement of the building work. If after the restricted building work commences the named licensed building practitioner(s) ceases to be engaged to carry out or supervise the restricted building work under the building consent, this must also be advised in writing as must also the details of any other licensed building practitioner(s) subsequently engaged to carry out or supervise the restricted building work (Section 87 of the Building Act 2004). A form "Advice of licensed building practitioner(s)" is enclosed for you to use to advise the Council of licensed building practitioner details.

Please also note that it is an offence to engage another person to carry out or supervise restricted building work who is not a licensed building practitioner (Section 86 of the Building Act 2004).

Other reference material

- Guide for completing an application for code compliance, <https://www.kapiticoast.govt.nz/your-council/planning/building/code-compliance-certificate/>
- A guide to the inspection process <https://www.kapiticoast.govt.nz/your-council/planning/building/building-services-inspections/>

If you have any questions regarding your building consent or your responsibilities, please contact Kapiti Coast District Council on 04 296 4700 or toll free on 0800 486 486.

Building Consent

[Form 5, Building (Forms) Regulations 2004]

240320

Section 51, Building Act 2004

The building

Street address of building: 198-200 Maungakotukutuku Road, Parapara

Legal description of land where

building is located: LOT 20 DP 33688

Valuation number: 1540004600

Building name:

Location of building within site/

block number:

Level/unit number:

The owner

Name of owner: Peter Saunders and Usani Saunders

Contact person: Peter Saunders

Mailing address: 200 Maungakotukutuku Road, Paraparaumu

Street address/registered office:

Phone numbers:

Landline: *Mobile:* 0212420309

After hours: *Fax number:*

Email address: pjsaunders@live.com

Website:

First point of contact for communications with the council/building consent authority:

Full Name: Seajay Consulting Engineers

Mailing Address: PO Box 1713, Paraparaumu 5254

Phones:: 021 121 4591: (04) 212 5150

Email: craig@seajay.co.nz

Building work

The following building work is authorised by this building consent:

The project comprises construction of a new set of internal stairs in the existing two storey house.

Detached Dwellings

This building consent is issued under section 51 of the Building Act 2004. This building consent does not relieve the owner of the building (or proposed building) of any duty or responsibility under any other Act relating to or affecting the building (or proposed building). This building consent also does not permit the construction, alteration, demolition, or removal of the building (or proposed building) if that construction, alteration, demolition, or removal would be in breach of any other Act.

Conditions of building consent

This building consent is subject to the following conditions:

1. Refer to the list of inspections required. Under section 90 of the Building Act 2004 agents authorised by the Council (acting as a Building Consent Authority) are entitled, at all times during normal working hours or while building work is being done, to inspect–
 - a. land on which building work is being or is proposed to be carried out; and
 - b. building work that has been or is being carried out on or off that building site; and
 - c. any building.

Compliance schedule

A compliance schedule is not required for the building.

Attachments

Copies of the following documents are attached to this building consent:

- List of required inspections and supporting documentation required
- Building Consent Addendum
- Plans and specifications

Note: The cover letter and all attachments to this building consent should be read fully to ensure you understand all conditions of this consent.



Signature

Building Officer

Position

On behalf of: KAPITI COAST DISTRICT COUNCIL

Date: 14/06/24

Relevant Information

Issued in accordance with Building Consent No. 240320

1. Plan notes take precedence over general specifications.

Building Consent Addendum to 240320

Application	Building Consent No. 240320
Seajay Consulting Engineers PO Box 1713 Paraparaumu 5254	

Project	
Description:	Dwellings - Alterations & additions Being Stage 1 of an intended 1 Stages The project comprises construction of a new set of internal stairs in the existing two storey house.
Intended Life:	Indefinite, but not less than 50 years
Intended Use:	Detached Dwellings
Estimated Value:	\$20,000
Location:	198-200 Maungakotukutuku Road, Paraparau
Legal Description:	LOT 20 DP 33688
Valuation No:	1540004600

Contractor: Craig McGhie-Seajay Consulting Engineers PO Box 1713,
Paraparaumu : 04 2125150

Specific requirements

1. The inspection of all specific design components covered by a producer statement design (PS1), where the designer has recommended construction monitoring, is the responsibility of the Design Engineer who is also required to supply a written report (PS4) to the Council. It is the Design engineer's responsibility to confirm design assumptions.
2. Ground bearing must be reconfirmed on site following excavation but prior to placing of concrete and reinforcing.

KAPITI COAST DISTRICT COUNCIL

Consent No: 240320

Building Category: R1

Site Address: 198-200 Maungakotukutuku Road, Paraparau

Owner/Agent: Seajay Consulting Engineers

Inspections

The following inspections are required:

- 1 Preline Building
- 1 Final Inspection
- 2 Total Inspections

Residential Documentation

- 1 Application for CCC
- 1 Construction review PS4 statement for structural engineering

GENERAL NOTES:

1. CONFIRM EXISTING STRUCTURE ON SITE.
2. DO NOT SCALE OFF DRAWINGS. ALL DIMENSIONS TO BE CONFIRMED ON SITE.
3. MATERIALS AND WORKMANSHIP SHALL BE THE BEST OF THEIR RESPECTIVE KIND COMPLYING WITH ALL RELEVANT NEW ZEALAND STANDARDS AND MANUFACTURERS SPECIFICATIONS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL MATERIALS AND PREFABRICATED COMPONENTS ARE SUPPLIED, STORED, HANDLED AND ERECTED IN A MANNER THAT DOES NOT DISTORT OR DAMAGE THE MATERIAL OR COMPONENTS OR THEIR CONNECTIONS AND SURFACE COATINGS. THE CONTRACTOR SHALL MAKE GOOD ANY DAMAGE AT THEIR EXPENSE.
4. PRODUCT SUBSTITUTIONS SHALL NOT BE MADE OR ALTERNATIVE DETAILS USED WITHOUT PRIOR APPROVAL FROM THE ENGINEER. WORK SHALL BE CONSTRUCTED STRICTLY IN ACCORDANCE WITH APPROVED DRAWINGS. THE CONTRACTOR SHALL CONTACT THE ENGINEER FOR CLARIFICATION PRIOR TO UNDERTAKING ANY WORK IF THEY CONSIDER THAT THERE ARE ANY ERRORS, DISCREPANCIES OR AMBIGUITIES IN THE DRAWINGS OR UNFORESEEN SITE CONDITIONS MAKE DETAILS IMPRACTICAL TO CONSTRUCT.
5. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THE STRUCTURE IS ADEQUATELY SUPPORTED DURING CONSTRUCTION.
6. ACCESS TO SITE, CONTROL OF SITE ACTIVITIES AND ALL WORK SHALL BE UNDERTAKEN IN A SAFE MANNER COMPLYING WITH THE HEALTH AND SAFETY AT WORK ACT 2015, HEALTH AND SAFETY AT WORK REGULATIONS 2016 AND WORK SAFE NEW ZEALAND APPROVED CODES OF PRACTICE, GOOD PRACTICE GUIDELINES AND FACT SHEETS AS APPLICABLE.
7. CONTRACTOR TO LOCATE ALL UNDERGROUND AND BUILDING SERVICES PRIOR TO COMMENCING AND PROTECT AS NECESSARY.

FOUNDATION NOTES:

8. ENSURE THAT FOOTINGS ARE FOUNDED ON SOLID GROUND HAVING A MINIMUM ULTIMATE BEARING CAPACITY NOT LESS THAN 300kPa UNLESS NOTED OTHERWISE. CONFIRM ON SITE WITH ENGINEER.
9. A MINIMUM OF 150mm FREE DRAINING BASE COURSE SHALL BE PLACED UNDER ANY SLABS. BASECOURSE SHALL BE A WELL GRADED AP20 WITH NOT MORE THAN 5% PASSING A 2.2mm SIEVE. PROVIDE MINIMUM 25mm COMPACTED SAND BLINDING TO PROTECT DPM.
10. EXCAVATIONS SHALL BE KEPT FREE OF WATER AT ALL TIMES.
11. REMOVE SURPLUS MATERIAL FROM SITE.

CONCRETE NOTES:

12. CONCRETE WORK SHALL COMPLY WITH THE REQUIREMENTS OF NZS3109 AND NZS 3604.
13. CONCRETE SHALL BE GRADE N25 (25MPa) AND HAVE A MAXIMUM SLUMP OF 100mm.
14. ALL REINFORCING STEEL SHALL COMPLY WITH AS/NZS4671. BARS DENOTED "HD" SHALL BE GRADE 500E. BARS DENOTED "D" or "R" SHALL BE GRADE 300E. MESH SHALL BE GRADE 500E.
15. MINIMUM CONCRETE COVER SHALL BE:

• INTERIOR FORMWORK/SLAB

50mm

• IN CONTACT WITH GROUND

75mm
16. LAPS IN REINFORCING STEEL SHALL BE LOCATED AND DETAILED AS SHOWN ON THE DRAWINGS. THE CONTRACTOR SHALL PROVIDE DETAILS OF ANY ADDITIONAL LAPS THEY REQUIRE FOR APPROVAL BY THE ENGINEER PRIOR TO FABRICATING THE STEEL. MINIMUM STEEL LAPS SHALL BE:

GRADE 300E (D)

GRADE 500E (HD)

• 10mm DIAMETER

500mm

700mm

• 12mm DIAMETER

600mm

850mm

17. REINFORCING BARS BENT OR FABRICATED ON SITE SHALL BE FABRICATED USING APPROPRIATE EQUIPMENT DESIGNED FOR BENDING REINFORCING STEEL. BEND RADIUS SHALL COMPLY WITH NZS3109. HD BARS SHALL NOT BE RE-BENT.

18. SURFACE FINISHES SHALL BE, UNLESS SHOWN OTHERWISE ON THE ARCHITECTURAL DRAWINGS:

• SLABS

U3

• EXPOSED FORMWORK

F4

19. ALL CONCRETE SHALL BE PLACED AND COMPACTED WITH AN EMERSION VIBRATOR OR SIMILAR APPROVED. RODDING CONCRETE IS NOT AN ACCEPTABLE METHOD OF COMPACTION.

20. CONCRETE SHALL BE CURED IN ACCORDANCE WITH NZS3109 FOR A MINIMUM PERIOD OF 7 DAYS.

21. HOLDING DOWN BOLTS, WELD PLATES AND CAST IN ITEMS SHALL BE CAST INTO THE SLABS, FOOTINGS, WALLS AND BEAMS. BOLTS SHALL BE BENT TO PREVENT ROTATION. BOLTS, WELD PLATES AND CAST IN ITEMS SHALL BE LOCATED WITH AN APPROPRIATE TEMPLATE HELD RIGIDLY IN PLACE DURING THE CONCRETE POUR. PROPRIETARY CHEMICAL OR MECHANICAL BOLT FIXING SHALL NOT BE SUBSTITUTED WITHOUT APPROVAL OF THE ENGINEER.

22. CAST IN ITEMS SHALL BE LOCATED WITH ±5mm OF THE DESIGN PLAN POSITION AND HEIGHT.

23. RAMSET EPCON C6 EPOXY GROUT (OR SIMILAR APPROVED) SHALL BE USED FOR ALL DRILLED AND EPOXY GROUTED ITEMS AND FIXINGS WHERE SHOWN ON THE DRAWING OR APPROVED BY THE ENGINEER.
- STEEL NOTES:
24. STEELWORK TO BE SUPPLIED, FABRICATED AND INSTALLED IN ACCORDANCE WITH NZS 3404.

25. THE CONTRACTOR SHALL SUPPLY SHOP DRAWINGS FOR REVIEW AND COMMENT BY THE ENGINEER PRIOR TO COMMENCING FABRICATION OF THE STEEL WORK. THESE SHALL INCLUDE ALL PROPOSED WELD PREPARATION AND WELD TYPES.

26. ALL WELDS TO BE 6 FILLET WELDS ALL ROUND UNLESS NOTED OTHERWISE.

27. ALL M12 BOLTS TO BE GRADE 4.6. ALL M16 BOLTS TO BE GRADE 8.8 UNLESS NOTED OTHERWISE.

28. ALL PLATES TO BE 10mm THICK UNLESS NOTED OTHERWISE.

29. ALL STEEL SECTIONS TO BE PROVIDED WITH 14 DIAMETER HOLES AT 800mm CENTRES IN THE FLANGES AND WEBS FOR FIXING TIMBER FRAMING.

30. STEEL GRADES:

• PLATES

250 MPa

• HOT ROLLED SECTIONS

300 MPa

• HOLLOW SECTIONS

350 MPa

31. ALL WELD ELECTRODES ARE E48XX OR W50X. WELDING, PLANT, INSTRUMENTS AND ACCESSORIES SHALL COMPLY WITH AS/NZS1554.1. WELDERS SHALL BE QUALIFIED TO AS/NZS 2980.

32. ALL INTERNAL STRUCTURAL STEEL TO BE PAINTED IN ACCORDANCE WITH SYSTEM DESIGNATION AS/NZS2312/AKL1 BEFORE DELIVERY TO SITE. ANY AREAS DAMAGED TO BE MADE GOOD UPON INSTALLATION AND FOLLOWING SITE WELDING. TOP COAT AND COLOUR TO OWNER REQUIREMENTS

33. WELD INSPECTIONS(IF REQUIRED) SHALL BE CARRIED OUT BY QUALIFIED WELDING INSPECTOR. CONTRACTOR SHALL PROVIDE A WELD INSPECTION CERTIFICATE IF REQUESTED. THE ENGINEER SHALL BE GIVEN THE OPPORTUNITY TO INSPECT WELDING. REJECTED WELDING SHALL BE REMOVED AND RE-WELDED AT THE CONTRACTORS EXPENSE.

34. ALL WELDS VISIBLE IN FINAL STRUCTURE TO BE SMOOTH AND/OR GROUND FLUSH TO ACHIEVE A SMOOTH SURFACE FINISH.
- TIMBER NOTES:
35. TIMBER WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING STANDARDS:

NZS 3602

TIMBER AND WOOD-BASED PRODUCTS FOR USE IN BUILDING

NZS 3603

TIMBER STRUCTURES STANDARD

NZS 3604

TIMBER FRAME BUILDINGS

NZS 3605

TIMBER PILES AND POLES FOR USE IN BUILDING

AS/NZS 1328.1 & 2

GLUED LAMINATED STRUCTURAL TIMBER

AS/NZS 2269.0

PLYWOOD STRUCTURAL PART 0

36. TIMBER SHALL BE MSG8 OR VSG8 UNLESS NOTED OTHERWISE ON THE DRAWINGS.

37. TIMBER SHALL BE INSTALLED WITH A MOISTURE CONTENT WITHIN THE PERMITTED RANGES SHOWN IN NZS 3602 AND THE LIKELY IN-SERVICE MOISTURE CONTENT REQUIRED TO PREVENT EXCESSIVE LONG TERM SHRINKAGE.

38. PROPRIETARY TIMBER PRODUCTS AND GLU LAMINATED TIMBER MEMBERS SHALL BE CLEARLY MARKED ON THE MEMBER WITH MARKINGS DENOTING THE - "MANUFACTURER", "PRESERVATIVE TREATMENT" AND "STRENGTH GRADE". UNIDENTIFIED TIMBER SHALL BE REMOVED AND REPLACED AT THE CONTRACTORS EXPENSE WITH COMPLIANT TIMBER.

39. ALL TIMBER SHALL BE WORKED AND CUT TO BE TRUE AND SQUARE AND FREE FROM WANE AND WARP WITH ALL JOINTS MATCHING AND MATING TO A PROPER CONTACT FIT.

40. ALL CONNECTIONS WHETHER NAILED, SCREWED, GLUED, MORTICED OR DOVETAILED SHALL BE ACCURATELY MADE AND PROPERLY EXECUTED TO PROVIDE SOUND SATISFACTORY CONNECTIONS FOR THE CLASS OF WORK REQUIRED. TIMBERS CONTAINING DEFECTS OR DISTORTIONS SHALL NOT BE CRAMPED TO PROVIDE MATING AT CONNECTIONS BUT SHALL BE DISCARDED AND REPLACED BY TRUE DEFECT-FREE TIMBERS BEFORE CONNECTIONS ARE MADE.

41. PROVIDE AND INSTALL TO GOOD TRADE PRACTICE ALL NECESSARY FIXINGS AND CONNECTIONS (NAILS, BOLTS, SCREWS, ADHESIVES, PROPRIETARY MECHANICAL FIXINGS ETC) REQUIRED FOR THE FABRICATION AND ERECTION OF ALL TIMBER WORK.TIMBER CONNECTIONS NOT SHOWN TO BE IN ACCORDANCE WITH NZS3604.

42. ALL BOLTED TIMBER CONNECTIONS TO HAVE :

• 10mm DIA BOLTS TO HAVE 38x38x3 SQUARE WASHER

• 12mm DIA BOLTS TO HAVE 50x50x3 SQUARE WASHER

• 16mm DIA BOLTS TO HAVE 65x65x5 SQUARE WASHER

43. WASHER AND BOLT HEADS SHALL NOT BE CHECKED INTO THE TIMBER. CONTRACTOR SHALL COORDINATE BRACKET AND CLEAT ORIENTATION WITH SUB-TRADES TO ENSURE THAT CHECKING IN OF BOLTS AND WASHER IS NOT REQUIRED. TIMBER THAT HAS BEEN CHECKED FOR WASHER AND BOLTS HEADS SHALL BE REMOVED AND REPLACED AT THE CONTRACTOR EXPENSE.

44. TIMBER MEMBERS SHALL NOT BE NOTCHED AT THEIR EDGES UNLESS SHOWN OTHERWISE ON THE DRAWINGS OR APPROVED BY THE ENGINEER.

45. TIMBER TREATMENT TO TCP SPECIFICATIONS, UNLESS SHOWN OTHERWISE ON ARCHITECTURAL DRAWINGS, SHALL BE :

• EMBEDDED IN GROUND

H5

• IN CONTACT WITH GROUND

H4

• EXTERIOR TIMBER NOT IN CONTACT WITH GROUND

H3.2

• INTERIOR

H1.2

46. ALL NAILS, SCREWS , BOLTS, WASHERS, PLATES AND BRACKETS SHALL BE GRADE 304 OR 316 STAINLESS STEEL IN CORROSION ZONE D AND/OR COASTAL ENVIRONMENT WHERE EXPOSED WEATHER OR IN A SUBFLOOR SPACE OR IN ANY ENVIRONMENT WITHIN 300mm OF THE GROUND. LIGHT GAUGE STEEL BRACKETS AND FIXINGS SHALL BE GRADE 304 OR 316 STAINLESS STEEL WHERE EXPOSED WEATHER OR IN A SUBFLOOR SPACE IN ANY ENVIRONMENT.

47. STAIR TREADS TO BE A HARDWOOD TO OWNERS SELECTION. CONFIRM ON SITE.
- ENGINEERS DESIGN
- This project contains elements specifically designed by an engineer. The owner/builder is required to ensure the engineer inspects the work and provides KCDC with written evidence of the inspection.
- ENGINEER STRUCTURAL DESIGN
TAKES PRECEDENCE
- CAUTION
Plans have been digitally reproduced and may not be to scale.
- BC240320
- Further Information Received
14/06/2024
- | REV: | DESCRIPTION: | ISSUED: | DATE: |
|------|--|---------|-----------|
| 2 | PRJCT NO. CORRECTED - FOR CONSENT/CONSTR | CJM | JUNE 2024 |
- SCHEDULE OF INSPECTIONS
- SEAJAY CONSULTING ENGINEERS LTD HAVE BEEN ENGAGED TO UNDERTAKE CONSTRUCTION MONITORING OF THE SPECIFIC ENGINEERING DESIGN ITEMS TO A IPENZ /ACENZ CM3 LEVEL AND PROPOSE TO UNDERTAKE THE FOLLOWING SITE INSPECTIONS :
- | | | |
|---|--------------------------------|---|
| 1 | EXISTING STRUCTURE | WHEN EXPOSED TO VIEW |
| 2 | FOUNDATION SUBGRADE | PRIOR TO PLACING REINFORCING STEEL |
| 3 | PAD FOOTINGS | PRE-POUR |
| 4 | INTERNAL BEAMS AND CONNECTIONS | PRE-LINE OR PRIOR TO BUILDING IN TO SUCH AN EXTENT THAT REMEDIATION WORK COULD NOT BE CARRIED OUT |
| 5 | INTERNAL POSTS AND CONNECTIONS | PRE-LINE OR PRIOR TO BUILDING IN TO SUCH AN EXTENT THAT REMEDIATION WORK COULD NOT BE CARRIED OUT |
| 6 | STAIR STRUCTURE | PRE-CLAD OR PRIOR TO BUILDING IN TO SUCH AN EXTENT THAT REMEDIATION WORK COULD NOT BE CARRIED OUT |
| 7 | BALUSTRADES | ON COMPLETION AND/OR PROIR TO COVERING CONNECTIONS |
| 8 | RELOCATED BRACING | ON COMPLETION |
- INSPECTION NOTES:
- A. INSPECTIONS SHALL NOT BE UNDERTAKEN IF A BUILDING CONSENT HAS NOT BEEN GRANTED BY THE BUILDING CONSENT AUTHORITY .

B. THE ABOVE ITEMS OF INSPECTIONS ARE THE MINIMUM REQUIRED TO ENABLE SEAJAY CONSULTING ENGINEERS LTD TO ISSUE A PS4 - PRODUCER STATEMENT CONSTRUCTION REVIEW FOR THE SPECIFIC ENGINEERING DESIGN ITEMS.

C. THE ABOVE ITEMS OF INSPECTION DO NOT COVER WORK CONSTRUCTED IN ACCORDANCE WITH NZS 3604:2011, FOR WHICH INSPECTIONS ARE TO BE UNDERTAKEN BY THE BUILDING CONSENT AUTHORITY .

D. SPECIFIC DESIGN WORK IS TO BE INSPECTED BY THE ENGINEER PRIOR TO CLOSING IN OR BUILDING IN TO THE POINT WHERE REMEDIAL WORK CANNOT BE CARRIED OUT. THE ENGINEER REQUIRES 48 HOURS NOTICE BEFORE ANY INSPECTIONS.. THE ABOVE TIMEFRAME IS INDICATIVE, THE ENGINEER AND CONTRACTOR ARE TO AGREE THE TIMING OF INSPECTION PRIOR TO WORK COMMENCING ON SITE.


6. THE CONTRACTOR SHALL PROVIDE SAFE AND REASONABLE ACCESS TO THE SITE AND STRUCTURAL ELEMENTS TO BE INSPECTED. THE ENGINEER SHALL BE SOLELY RESPONSIBLE FOR DEEMING COMPLIANCE WITH THIS REQUIREMENT AND WILL NOT UNDERTAKE INSPECTIONS IF THEY DEEM IT NOT SAFE TO DO SO.

E. THE ABOVE SCHEDULE DOES NOT NECESSARILY REPRESENT THE ACTUAL NUMBER OF INSPECTIONS TO BE UNDERTAKEN. THE NUMBER OF INSPECTIONS WILL DEPEND ON THE CONSTRUCTION METHOD, SEQUENCE OF THE WORKS AND WHETHER OR NOT UNFORESEEN CONDITIONS OR DIFFICULTIES ARE ENCOUNTERED ON SITE.


F. THE BUILDING CONSENT AUTHORITY SHALL BE NOTIFIED OF THE REQUIREMENT FOR AN INSPECTION OF SPECIFIC DESIGN ITEMS AND AFFORDED THE OPPORTUNITY TO INSPECT.

G. THE CONTRACTOR/BUILDER SHALL SEEK WRITTEN APPROVAL TO USE ALTERNATIVE DETAILS OR PRODUCTS PRIOR TO UNDERTAKING THE WORK. WORK FOUND ON SITE NOT COMPLYING EXACTLY WITH THE APPROVED DRAWINGS AND SPECIFICATIONS WILL FAIL THE INSPECTION AND A PRODUCER STATEMENT PS4 WILL NOT BE ISSUED UNTIL REMEDIAL WORK IS COMPLETED. COST OF REDESIGN AND/OR RE-INSPECTION SHALL BE CHARGED AS A VARIATION AS NECESSARY .
- APPROVED BY
BUILDING
simonc
OFFICER
14/06/2024
- | | | | | |
|--|--|---------------------------------|----------------------|--------------------|
|  <div>42 MICHAEL, ROAD, PO BOX 1713, PARAPARAUMU 5252 PH (04) 212 5150 -
M: 021 121 4591 - craig@seajay.co.nz</div> | CLIENT:
PETER SAUNDERS | DRAWN:
CJM | DATE:
FEB 2024 | SCALE:
AS SHOWN |
| | PROJECT:
200 MAUNGAKOTUKUTUKU ROAD
PARAPARAUMU | PROJECT NO.
<div>23020</div> | | |
| | TITLE:
NEW STAIRS
GENERAL NOTES | SHEET NO.
<div>S1</div> | REV:
<div>2</div> | |
| | 23020.dwg | | | |

REV:	DESCRIPTION:	ISSUED:	DATE:
2	PRJCT NO. CORRECTED - FOR CONSENT/CONSTR	CJM	JUNE 2024



EXISTING GROUND FLOOR PLAN
1:100



EXISTING 1ST FLOOR PLAN
1:100

BC240320
Further Information Received
14/06/2024

- NOTES:**
- 1. REFER SHEET S1 FOR GENERAL NOTES
 - 2. CONFIRM ALL DIMENSIONS ON SITE

 CONSULTING ENGINEERS CIVIL • STRUCTURAL • FIRE 42 MICHAEL ROAD, PO BOX 1713, PARAPARAUMU 5252 PH (04) 212 5150 - M: 021 121 4591 - craig@seajay.co.nz	CLIENT: PETER SAUNDERS	DRAWN: CJM	DATE: FEB 2024	SCALE: AS SHOWN
	PROJECT: 200 MAUNGAKOTUKUTUKU ROAD PARAPARAUMU	PROJECT NO. 23020		
	TITLE: NEW STAIRS EXISTING PLANS	SHEET NO. S2	REV: 2	
	23020.dwg			



1:100



1:100

BC240320
Further Information Received
14/06/2024




1:50



NOTES:

1. REFER SHEET S1 FOR GENERAL NOTES
2. CONFIRM ALL DIMENSIONS ON SITE

 Seajay CONSULTING ENGINEERS CIVIL • STRUCTURAL • FIRE 42 MICHAEL ROAD, PO BOX 1713, PARAPARAUMU 5252 PH (04) 212 5150 - M: 021 121 4591 - craig@seajay.co.nz	CLIENT: PETER SAUNDERS	DRAWN: CJM	DATE: FEB 2024	SCALE: AS SHOWN
	PROJECT: 200 MAUNGAKOTUKUTUKU ROAD PARAPARAUMU	PROJECT NO. 23020		
	TITLE: NEW STAIRS PROPOSED PLAN	SHEET NO. S3	REV: 2	
		23020.dwg		





REV:	DESCRIPTION:	ISSUED:	DATE:
2	PRJCT NO. CORRECTED - FOR CONSENT/CONSTR	CJM	JUNE 2024



NOTES:

1. REFER SHEET S1 FOR GENERAL NOTES
2. CONFIRM ALL DIMENSIONS ON SITE





BC240320
Further Information Received
14/06/2024



CLIENT: PETER SAUNDERS	DRAWN: CJM	DATE: FEB 2024	SCALE: AS SHOWN
PROJECT: 200 MAUNGAKOTUKUTUKU ROAD PARAPARAUMU	PROJECT NO. 23020		
TITLE: NEW STAIRS DETAILS 1	SHEET NO. S5	REV: 2	


23020.dwg








 42 MICHAEL, ROAD, PO BOX 1713, PARAPARAUMU 5252 PH (04) 212 5150 - M: 021 121 4591 - craig@seajay.co.nz	CLIENT: PETER SAUNDERS	DRAWN: CJM	DATE: FEB 2024	SCALE: AS SHOWN
	PROJECT: 200 MAUNGAKOTUKUTUKU ROAD PARAPARAUMU	PROJECT NO. 23020		
	TITLE: NEW STAIRS DETAILS 3	SHEET NO. S7	REV: 2	
		23020.dwg		

REV:	DESCRIPTION:	ISSUED:	DATE:
2	PRJCT NO. CORRECTED - FOR CONSENT/CONSTR	CJM	JUN 2024



BC240320
Further Information Received
14/06/2024

SECTION C 1:25 S3



NOTES:


1. REFER SHEET S1 FOR GENERAL NOTES
2. CONFIRM ALL DIMENSIONS ON SITE
3. SELF TAPPING TEC SCREWS MAY BE USED IN LIEU OF GUTTER BOLTS FOR BRACKETS A & B CONNECTIONS.



CLIENT: PETER SAUNDERS	DRAWN: CJM	DATE: FEB 2024	SCALE: AS SHOWN
PROJECT: 200 MAUNGAKOTUKUTUKU ROAD PARAPARAUMU	PROJECT NO. 23020		
TITLE: NEW STAIRS DETAILS 4	SHEET NO. S8	REV: 2	

23020.dwg

Figure 26: Handrail Profiles and Clearances
Paragraphs 6.0.8 and 6.0.9



BC240320
Further Information Received
14/06/2024

6.0.2 Any *stairway* which exceeds 2.0 m in width shall:

- a) Have *handrails* on both sides and, where the width exceeds 4.0 m, shall also have an intermediate *handrail* provided at the centre of the *stairway*, or
- b) If the *stairway* is essentially an outdoor architectural feature and not required to be an *accessible stairway*, have at least one *handrail*. Examples of such *stairways* are those leading to civic areas, or to decks on *Housing*.

COMMENT:

A central rail gives all users a rail to use for safety purposes. On *stairways* in public *buildings*, such as sports stadia, intermediate rails are also effective for crowd control. The 2.0 m width is a comfortable width for three people, two of whom can grasp a rail if anyone trips.

6.0.3 Accessible stairways and accessible ramps – *Handrails* shall be provided on both sides of *accessible stairways* and on both sides of *accessible ramps* where the ramp slope is steeper than 1 in 20. The *handrails* shall be continuous except where doors are located on landings (see Figures 9 and 25).

6.0.4 Slope of handrails – *Handrails* shall have the same slope as the *pitch line*, begin no further than the second riser from the lower end of the *stairway*, and extend the full length of the *stairway* they serve. Except that, where the *handrail* serves an *accessible stairway* or *accessible ramp*, a 300 mm (minimum) horizontal extension shall be provided at each end of the *handrail*, as shown in Figures 9 and 25.

6.0.5 The first riser shall be located a sufficient distance back from the corner where the two walls meet, to accommodate the extended *handrail*, as shown in Figure 25.

6.0.6 Height of handrails – *Handrails* shall be positioned between 900 mm and 1 m above the *pitchline* (see Figure 25) measured to the top of the *handrail*.

COMMENT:

Where a *handrail* is located on top of the barrier of a *stairway* flight it may transition to a height of 1100 mm on an intermediate landing.

6.0.7 Handrail profiles – *Handrails* shall have a profile which can be readily grasped by an adult hand and shall be installed in a way that avoids the likelihood of personal injury. An acceptable *handrail* shall be shaped and located to ensure that, under normal usage, a person's hand will not contact adjacent walls, supporting brackets or fixings, or any other obstruction.

COMMENT:

It is important that in the event of stumbling on a *stairway* or ramp an adult, even with a small hand, can firmly grasp the *handrail* to prevent a fall.

Amends
4 and 5

6.0.8 A graspable *handrail* profile shall have:

- a) A flat or convex upper surface,
- b) Arrised or radiused edges,
- c) A minimum cross section width of 20 mm, and
- d) A "relevant width" (as illustrated in Figure 26 (a)) across the top surface of no greater than 80 mm. Figure 26 (a) and (b) indicates some acceptable profiles but others may also be acceptable.

6.0.9 Acceptable *handrail* profiles for *accessible stairways* and *accessible ramps* are shown in Figure 26 (b).

COMMENT:


In most circumstances a *handrail* is used with a light grip to steady the user of a *stairway* or ramp. Ambulant people with disabilities use *handrails* for both leverage and support, and wheelchair users often need to firmly grip the rails to pull themselves along, particularly on ramps. In those circumstances a profile offering an adequate grip is important.

6.0.10 *Handrails* are not required on the steps between tiers of seating rows such as in cinemas and stadiums where the steps take the form of two risers with a tread between leading onto a landing alongside a row of seats. However, a *handrail* shall be provided alongside the steps that give access to the end of a row of seats. Steps shall have a common *stairway* or *accessible stairway* dimensions (see Figure 11).

Amend 6
Jan 2017

Amend 6
Jan 2017

BC240320
Further
Information
Received
14/06/2024



BC240320
Received by
Kapiti Coast District Council
31/05/2024



STRUCTURAL CALCULATIONS

For:

**NEW STAIRS
200 MAUNGAKOTUKUTUKU ROAD
PARAPARAUMU**

Preamble:

The project comprises constructing new internal stairs. These calculations pertain to the design of:

- a) Foundations : Pad footings to support stair posts
- b) Stairs : Structural frame and treads
- c) Balustrade : Structural support for metal balustrade

Note: Calculations are provided for Building Consent Authority information only. Construction details shown on the drawings and in the specification shall take precedence. Contractors/Builders shall follow the drawings and specification unless directed otherwise by the Engineer.

Project:	23020	Date:	6 February 2024
Report No:	SC01	Prepared:	C. McGhie
Revision:	1		NZCE, BE (Civil) Hon, ME (Fire) CPEng, CMEngNZ

Disclaimer:

This report has been prepared for the sole use of our client, Peter Saunders, for the particular brief for the proposed new stairs and on the terms and conditions agreed with our client. It may not be used or relied on (in whole or part) by anyone else, or for any other purpose or in any other contexts, without our prior written agreement. Seajay Consulting Engineers accepts no responsibility or liability for the consequences of the unauthorised use of this document.



New Zealand
Institute of Architects
Incorporated



BC240320
Received by
Kapiti Coast District Council
31/05/2024

21

Building Code Clause(s)..... B1

PRODUCER STATEMENT – PS1 – DESIGN

(Guidance on use of Producer Statements (formerly page 2) is available at www.engineeringnz.org)

ISSUED BY: Seajay Consulting Engineers Ltd
(Design Firm)

TO: Peter Saunders
(Owner/Developer)

TO BE SUPPLIED TO: Kapiti Coast District Council
(Building Consent Authority)

IN RESPECT OF: New stairs
(Description of Building Work)

AT: 200 Maungakotukutuku Road, Paraparaumu
(Address)

Town/City: Paraparaumu LOT 20 DP 33688 SO
(Address)

We have been engaged by the owner/developer referred to above to provide:

structural design services and construction monitoring of specifically designed elements - Concrete pad footings, Structural frame and treads for new stairs, structural support for metal balustrade and relocate existing cross bracing

(Extent of Engagement)

services in respect of the requirements of Clause(s)..... B1 of the Building Code for:

☐ All or ☒ Part only (as specified in the attachment to this statement), of the proposed building work.

The design carried out by us has been prepared in accordance with:

☒ Compliance Documents issued by the Ministry of Business, Innovation & Employment..... B1/VM1 & VM4or
(verification method/acceptable solution)

☐ Alternative solution as per the attached schedule.....

The proposed building work covered by this producer statement is described on the drawings titled:

200 Maungakotukutuku Rd, Paraparaumu, New stairs and numbered 23020 - S1 to S8
together with the specification, and other documents set out in the schedule attached to this statement.

On behalf of the Design Firm, and subject to:

- (i) Site verification of the following design assumptions Existing structure, ground bearing capacity of 300kPa
(ii) All proprietary products meeting their performance specification requirements;

I believe on reasonable grounds that a) the building, if constructed in accordance with the drawings, specifications, and other documents provided or listed in the attached schedule, will comply with the relevant provisions of the Building Code and that b), the persons who have undertaken the design have the necessary competency to do so. I also recommend the following level of construction monitoring/observation:

☐ CM1 ☐ CM2 ☒ CM3 ☐ CM4 ☐ CM5 (Engineering Categories) or ☐ as per agreement with owner/developer (Architectural)

I, Craig McGhie am: ☒ CPEng 173345 # ☐ Reg Arch #
(Name of Design Professional)

I am a member of: ☒ Engineering New Zealand ☐ NZIA and hold the following qualifications: NZCE, BE(Civil)Hon, ME(Fire)

The Design Firm issuing this statement holds a current policy of Professional Indemnity Insurance no less than \$200,000*.

The Design Firm is a member of ACENZ: ☐

SIGNED BY Craig McGhie (Signature)
(Name of Design Professional)

ON BEHALF OF Seajay Consulting Engineers Ltd Date: 6/2/2024
(Design Firm)

Note: This statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provided to the Building Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of \$200,000*.

This form is to accompany Form 2 of the Building (Forms) Regulations 2004 for the application of a Building Consent.
THIS FORM AND ITS CONDITIONS ARE COPYRIGHT TO ACENZ, ENGINEERING NEW ZEALAND AND NZIA

Project: 23020

**Memorandum from licensed building practitioner:
Certificate of design work
Section 45 and Section 30C, Building Act 2004**

OWNER: Peter Saunders

BUILDING: 200 Maungakotukutuku Road
Paraparaumu



42 Michael Rd, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

BASIS FOR PROVIDING THIS MEMORANDUM

I am providing this memorandum in my role as the Specialist designer who supervised and/or undertook specific elements of Restricted Building Work (RBW) design work as outlined in this memorandum – other designers will be providing a memorandum covering the remaining RBW design work.

IDENTIFICATION OF DESIGN WORK THAT IS RESTRICTED BUILDING WORK

I, Craig McGhie, supervised/undertook the following design work that is restricted building work:

PRIMARY STRUCTURE: B1

Design work that is Restricted Building Work		Description (Specific Engineering Design outside of the scope of NZS 3604:2011, unless noted otherwise).
Foundations	✓	Pad footings to support stairs
Walls	x	
Retaining Walls	x	
Beams	x	
Columns	x	
Bracing	✓	Relocated existing steel bracing
Other (Stairs)	✓	Structural stair frame, treads and associated connections
Other (Balustrade)	✓	Balustrade and associated connections

WAIVERS AND MODIFICATIONS

No waivers or modifications of the building code are required.

ISSUED BY

Design Entity/Company : Seajay Consulting Engineers Limited
Name: Craig McGhie

BC240320
Received by
Kapiti Coast District Council
31/05/2024

CPEng number: 173345

DECLARATION

I, Craig McGhie, LBP, state that I have applied the skill and care reasonably required of a competent design professional in supervising the Restricted Building Work (RBW) described in this form, and that based on this, I also state that the RBW:

- Complies with the building code; or
- Complies with the building code subject to any waiver or modification of the building code recorded on this form.

Signature: 

Date: 6/2/2024

CALCULATIONS

Project No.: 23020

Date:

Eng:

Page:

Project:

200 Maungakotukutuku Road

Description:

New Stairs

Seajay C
 CONSULTING ENGINEERS
 CIVIL • STRUCTURAL • FIRE
 42 Michael Road, PO Box 1713, Paraparaumu 5252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 email@seajay.co.nz

INDEX

1.0 GENERAL	1
1.1 Scope	1
1.2 Reference Codes & Standards	1
1.3 Structural System	1
1.4 Safety by Design Assessment	2
2.0 GEOMETRY	3
3.0 DESIGN LOADS	10
4.0 STAIR STRUCTURE	14
4.1 Geometry	14
4.2 Stair Model	18
4.3 Deflection	29
4.4 Member Strength	32
5.0 EXISTING STRUCTURE TO SUPPORT STAIRS	49
6.0 BALUSTRADES	63
6.1 Stair Balustrade Geometry	63
6.2 1st Floor Walkway Balustrade Geometry	64
6.3 Balustrade Loading	65
6.4 Infill Design	65
6.5 Top & Bottom Rail	67
6.6 Top Rail	68
6.7 Posts	76

BC240320

Received by

Kapiti Coast District Council

31/05/2024

Job No.: 23020


Project : 200 Maungakotukutuku Road

Description : New Stair

Page: 1

Date : 11/10/2023

Eng: CJM

**1.0 GENERAL****1.1 Scope**

The project comprises construction of a new set of stairs in the existing two storey house at 200 Maungakotukutuku Road, Paraparaumu. The existing house was designed and constructed in 1972.

These calculations pertain to the design of:

- a) Stair structural frame
- b) Stair treads
- c) Balustrade
- d) Design check existing structure and foundations to support new stair

BC240320
Received by
Kapiti Coast District Council
31/05/2024

1.2 Reference Codes and Standards

Building Code Clauses: ☒ B1/VM1 ☐ B1/VM2 ☐ B1/VM3 ☒ B1/VM4 ☐ E1/VM1

Design Standards:

- ☒ AS/NZS 1170 Structural; Design
- ☒ NZS 3101 Concrete Structures Standard
- ☒ NZS 3404 Steel Structures Standard
- ☒ NZS 3603 Timber Structures Standard
- ☒ NZS 3604 Timber Framed Building Standard
- ☐ NZS 4230 Design of Reinforced Concrete Masonry Structures Standard
- ☐ NZS 4229 Concrete Masonry Structure not requiring SED
- Other _____

1.3 Structural Systems

Gravity: ☒ Light Timber Frame ☒ Steel Frame/Members ☐ Concrete /Masonry Frame ☐ Concrete /Masonry Wall

Other _____

Lateral Load Resisting Systems:

Along

- ☒ Sheet Bracing Walls
- ☐ Steel Portals
- ☒ Steel X or K Braced Frames
- ☐ Concrete/Masonry MRF
- ☐ Concrete/Masonry Walls
- ☒ Floor Diaphragms
- ☐ Roof Plane Bracing
- ☐ Roof Diaphragm

Other Diagonal sarking to roof plane

Across

- ☒ Sheet Bracing Walls
- ☒ Steel Portals
- ☐ Steel X or K Braced Frames
- ☐ Concrete/Masonry MRF
- ☐ Concrete/Masonry Walls
- ☒ Floor Diaphragms
- ☐ Roof Plane Bracing
- ☐ Roof Diaphragm

Diagonal sarking to roof plane

Foundation Systems:

- ☐ Timber Piles and Subfloor
- ☐ Driven Piles
- ☐ Augured Piles
- ☒ Concrete Slab and Footings (on Piles if needed)
- ☐ Concrete Piles and Footing
- ☐ Concrete Ribbed Raft Slab

Other _____

1.4 Safety By Design Assessment

Project No. :	23020	SBD No.:	SBD01	Date:	11-Oct-23
Project:	New Stair			Page	2
Site Address:	200 Maungakotukutuku Road				



Project Description: The project comprises construction of a new set of stairs in the existing two storey house at 200 Maungakotukutuku Road, Paraparaumu. The existing house was designed and constructed in 1972.

Engineering Scope: Stair structural frame
Balustrade
Stair treads
Design check existing structure and foundations to support new stair

Safety/Risk Assessment

Items		Description	Score	Risk	Proposed Action
Foundation works	Likelihood	N/A			The overall risks are low and considered normal construction practice and risk. These risk are expected to be mitigated by:
	Consequence				
Internal structural	Likelihood	Tripping hazards, height and noise risks typical. Unlikely to occur to an extent to cause harm if managed.	2	L	*Compliance with Work safe Codes of Practice. *Use of qualified and experienced employees. *Use of suitable/correct plant and tools. *Contractor providing safe working environment.
	Consequence	Generally minor with appropriate construction precaution undertaken	2		
External structural works and decks	Likelihood	N/A			Therefore there are NO PROJECT SPECIFIC risks above and beyond normal design/construction practices that warrant SPECIFIC SAFETY DESIGN DETAILING.
	Consequence				
Soak pit	Likelihood				
	Consequence				
Other	Likelihood	Demolition of existing stairs by experienced contractor unlikely to result in incident	2	M	
	Consequence	Moderate risk of harm if accident involves a fall from height or collapse of structure on to person	3		
In use	Likelihood	Rare as construction will comply with Building Regulations	1	L	The building is a two storey house and as such the greatest risk pertaining to maintenance of building elements at height. The building owner will need to manage these risk by employing appropriate contractors and/or methods.
	Consequence	Consequence could range from trivial to Severe depending on how the home owner uses and/or maintains the property	4		
Decommissioning	Likelihood	Rare as building is a light weight structure that can easily be demolished with mobile plant	1	L	The structure would be expected to be demolished by an experienced contractor with appropriate mobile plant. Therefore there is a low risk.
	Consequence	Consequence could range from trivial to Severe depending on how the structure is demolished.	4		
Exceptional Risk	A				
	B				

Risk Matrix:

		Consequence					
		Trivial	Minor	Moderate	Major	Severe	
Score		1	2	3	4	5	
Likelihood	Almost Certain	5	M	H	H	E	E
	Likely	4	L	M	H	H	E
	Possible	3	L	M	M	H	E
	Unlikely	2	L	L	M	M	H
	Rare	1	L	L	L	L	M

Extreme Safety Risk Issue - Eliminate from design and/or notify Principal/Contractor for an agreed solution.

High Safety Risk Issue - Modify design where practicable and/or notify Principal/Contractor for an agreed solution.

Moderate Safety Risk Issue - Consider and/or implement design changes.



Low Safety Risk - Consider and/or mitigate as necessary within normal design practices.

Job No.: 23020
Project : 200 Maungakotukutuku Road
Description : New Stair


Page: 3
Date : 11/10/2023
Eng: CJM

Seajay C
CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

2.0 GEOMETRY




BC240320
Received by
Kapiti Coast District Council
31/05/2024




Existing Lower Plan 1:50

BC240320
Received by
Kapiti Coast District Council
31/05/2024




Proposed Lower Plan 1:50

BC240320
Received by
Kapiti Coast District Council
31/05/2024




Existing Upper Plan 1:50







BC240320
Received by
Kapiti Coast District Council
31/05/2024



Proposed Upper Plan 1:50



PROPOSED HOUSE FOR MR BERG - PARAPARAUMU



BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024

Job No.: 23020
 Project : 200 Maungakotukutuku Road
 Description : New Stair

Page: 10
 Date : 11/10/2023
 Eng: CJM



3.0 DESIGN LOADINGS

a) General [Refer AS/NZS 1170.0]

Importance Level: Normal Structures

2

Design Life:

50Years

Annual Probability of Exceedance:

Loadcase

APE:

ULS			SLS1	SLS2
Wind	Snow	EQ	All	EQ
500	250	500	25	N/A

b) Gravity [Refer AS/NZS 1170.1]

Occupancy: Domestic

	G	Q	PL
House floors	0.4 kPa	1.5 kPa	1.8 kN
Walls Timber	0.4 kPa		
Roofs	0.3 kPa	0.25 kPa	1.4 kN

Stair Structure & Treads	2.0 kPa	2.7 kN
Stair tread additional load case	2.2 kN/m	

Balustrades:	H	V	P _{H or V}
Top Rail	0.35 kN/m	0.35 kN/m	0.6 kN
Infill	0.5 kPa		0.25 kN

c) Wind [Refer AS/NZS 1170.2]

Site Wind Speed:

Wind Region

W

Wind Direction

NW

BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024

$V_{sit,\beta} = V_r M_d (M_{z,cat} M_s M_t)$

$V_{r,ULS} = 51 \text{ m/s}$ $V_{r,SLS} = 43 \text{ m/s}$

$M_d = 0.95$

$M_s = 1.0$ Shielding Multiplier (in range of 0.7 - 1.0)

Topographical Multipliers:

$E = 300 \text{ m}$ Site Elevation above Mean Sea Level

$M_h = 1.36$ Hill Shape Multiplier

$M_{Lee} = 1$

$M_e = 1.00$

$M_t = 1.36$

Cat 2 Terrain Category

Z 7 m

$M_{z,Cat} = 0.95$

$V_{sit,\beta} = 62.71 \text{ m/s}$

$V_{sit,\beta} = 52.9 \text{ m/s}$

$V_{ULS} = 62.71 \text{ m/s}$

$V_{SLS} = 52.9 \text{ m/s}$

$P_{zu} = 2359 \text{ Pa}$

$P_{zs} = 1677 \text{ Pa}$

NZS3604 Wind Zone Specific Design


Job No.: 23020
 Project : 200 Maungakotukutuku Road
 Description : New Stair

Page: 11
 Date : 11/10/2023
 Eng: CJM



NORTHERLY WIND DIRECTION GOVERN $M_d = 1.0$ (Pg 12)

Hill Shape Multiplier:



$L_1 = 198 \text{ m}$

$H/2L_u = 0.24$

$H/4 = 65$

$H/10 = 26$

$M_h = 1.0$

Where: $H/2L_u < 0.05$

$= 1 + \left\{ \frac{H}{3.5(z+L_1)} \right\} \left\{ \frac{1-x}{L_2} \right\}$ 1.362

Where: $0.05 < H/2L_u < 0.45$

$= 1 + 0.71 \left\{ \frac{1-x}{L_2} \right\}$ 1.710

Where: $0.45 < H/2L_u$ within separation zone

Mh = 1.362

BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024

Terrain Category:

Height of structure $z = 7 \text{ m}$

Averaging Distance $x_T = 500 \text{ m}$

Lag Distance $x_i = 140 \text{ m}$

Zone





Terrain Category (Cat)

Distance x_i

Zone 1	Zone 2	Zone 3	Zone 4
2	2	0	0
200	300	0	0

500 OK

Effective Terrain Category 2.00



Job No.: 23020
 Project : 200 Maungakotukutuku Road
 Description : New Stair

Page: 13
 Date : 11/10/2023
 Eng: CJM



DESIGN LOADINGS cont

c) Seismic [Refer NZS 1170.5]

Elastic Site Spectra:

$$C(T) = Ch(T) Z R N(T,D)$$

Soil Category Rock

Structure Period T1

Analysis Method

Spectral Shape Factor C(T)

Region/Town

Zone Factor Z

Nearest fault

Distance to Fault D

Limit State:

APE:

R

Near fault factor required:

Nmax (T)

N(T,D)

B

0.4 sec

Equivalent Static

1.89

Pareparaumu

0.4

Wellington

20 km

ULS	SLS	SLS II
500	25	N/A
1	0.25	N/A
No	No	N/A
1.00	1.00	N/A
1.00	1.00	N/A

C(T) = Ch(T) Z R N(T,D)	0.756	0.189	N/A
--------------------------------	--------------	--------------	------------

Horizontal Force Coefficient: Cd(T) = C(T) Sp/kμ

Ductility μ	3.5	1	1
Struct.Perf.Factor Sp	0.7	0.7	0.7
Scale factor kμ	2.429	1	1

Cd(T) = C(T) Sp/kμ	0.22	0.13	N/A
---------------------------	-------------	-------------	------------

NOTE: For equivalent static analysis deflections must be scaled in accordance with Section 6.2.3, NZS 1170.5

Summary of Horizontal Seismic Coefficients for Levels of Ductility:

μ ULS	1.0	1.25	1.5	2	3	4	5	6
Cd(T)	0.76	0.61	0.50	0.34	0.25	0.19	0.16	0.14

BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024

4.1 GEOMETRY


a) OVER ALL GEOMETRY

BC240320

Received by

Kapiti Coast District Council

31/05/2024



Stair to meet 'main private' stair requirements of DI/ASI being:

Going $\geq 280\text{mm}$


Riser $\leq 190\text{mm}$

Nosing 0-25mm

[FIG 11 & Table 6]
DI/ASI
Pg 15

Use 300 Tread + 20mm Nosing = 280 Going.

Figure 11: Pitch, Risers and Treads for Stairs
Paragraphs 4.1.1, 4.1.4, 4.4.2, 4.5.1 a) and Figure 17



Example of accessible stairway

For a riser height of 160mm, pitch line slope of 27° and tread projection of 25mm, the design tread depth is 340mm.

b) TREAD GEOMETRY

BC240320
Received by
Kapiti Coast District Council
31/05/2024




Figure 3: Barriers in areas likely to be frequented by children under 6 years of age
– glass or other solid material
Paragraph 1.2.1 a)






Figure 4: Stair barrier in an area likely to be frequented by children under 6 years of age
Paragraph 1.2.1 a)



4.2 STAIR MODEL & LOADS

SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED
 Path: C:\Users\Craig\Seajay - Documents\Project...\Design\Stairs only
 Designer: Date: Wednesday, November 22, 2023 11:45 AM, Page: 1



BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024


Materials:		Sections:	
		1	150x100x9 RHS
		2	75 PFC
		4	Section 4
	1	STEEL	
	2	Hardwood	



Viewpoint (-29,35)




a) Geometry




BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024

NODE NUMBERS




NODE NUMBERS

Materials: ☒ 1 STEEL ☐ 2 Hardwood
 Sections: ☒ 1 150x100x9 RHS ☒ 2 ☒ 4 Section 4



MEMBER NUMBERS

MEMBER NUMBERS





Materials: ☒ 1 STEEL ☐ 2 Hardwood
 Sections: ☒ 1 150x100x9 RHS ☒ 2 ☒ 4 Section 4

Load case 2

2 Q LIVE LOAD

$$Q = 2 \text{ kPa}$$



BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024




Viewpoint (-41,42), Loads

Materials: 1 STEEL 2 Hardwood
 Sections: 1 150x100x9 RHS 2 4 Section 4

b) Loads.

Load case 1

1 G - GRAVITY LOAD



Viewpoint (-41,42), Loads

BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024



Sections:
 1 150x100x9 RHS
 2
 4 Section 4

Materials:
 1 STEEL
 2 Hardwood

Load cases 3-8

(1) Point loads



- 3 P1
- 4 P2
- 5 P3
- 6 P4
- 7 P5
- 8 P6

Point Live Load

$$P = 2.7 \text{ kN}$$

$$P_H \text{ Balust} = 0.6 \text{ kN}$$

$$M_H = 0.66 \text{ kNm} \quad (P_3 \text{ 24})$$



separate load cases

BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024



Viewpoint (-41,42), Loads

Sections:
 1 150x100x9 RHS
 4 Section 4

Materials:
 1 STEEL
 2 Hardwood

Load case 9


■ 9 B1

Balustrade Load

$$H = 0.35 \text{ kN/m}$$

$$M_H = 0.385 \text{ kNm}$$

(Pg 24)



BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024



Viewpoint (-56,22), Loads

Materials: ■ 1 STEEL ■ 2 Hardwood
 Sections: ■ 1 150x100x9 RHS ■ 2 ■ 4 Section 4



CALCULATIONS

Project No. :

Date:

Eng:

Page:

24

Project:

Description:

Balustrade LoadsPer Tread. : Apply with UDL. & Point Loads

$$H = 0.28m \times 0.35 \text{ kN/m} = 0.098 \text{ kN}$$

$$V = 0.28m \times 0.35 \text{ kN/m} = 0.098 \text{ kN}$$


$$M_H = 0.098 \times 1.1m = 0.107 \text{ kNm}$$

Point Load only

$$P_H = 0.6 \text{ kN}$$

$$P_V = 0.6 \text{ kN}$$

$$M_H = 1.1 \times 0.6 = 0.66 \text{ kNm}$$



BC248320



Received by

Kapiti Coast District Council

31/05/2024

Load case 10

■ 10 1kN Vibration Check



BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024



Viewpoint (-56,22), Loads

Materials: ■ 1 STEEL ■ 2 Hardwood
 Sections: ■ 1 150x100x9 RHS ■ 2 ■ 4 Section 4

SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED

Path: C:\Users\Craig\Seajay\Seajay - Documents\Project...\Design\Stairs only

Designer: Date: Wednesday, November 22, 2023 12:29 PM, Page: 1

Filter: No filter

COMBINATION LOAD CASES

Load case 100: 1.2G&1.5Q

1.200 * Load case 1: G
1.500 * Load case 2: Q
1.500 * Load case 9: B1

Load case 101: 1.2G&1.5P1

1.200 * Load case 1: G
1.500 * Load case 3: P1

Load case 102: 1.2G&1.5P2

1.200 * Load case 1: G
1.500 * Load case 4: P2

Load case 103: 1.2G&1.5P3

1.200 * Load case 1: G
1.500 * Load case 5: P3

Load case 104: 1.2G&1.5P4

1.200 * Load case 1: G
1.200 * Load case 6: P4

Load case 105: 1.2G&1.5P5

1.200 * Load case 1: G
1.500 * Load case 7: P5

Load case 106: 1.2G&1.5P6

1.200 * Load case 1: G
1.500 * Load case 8: P6

Load case 200: G&0.7Q

1.000 * Load case 1: G
0.700 * Load case 2: Q

Load case 201: G&0.7P1

1.000 * Load case 1: G
0.700 * Load case 3: P1

Load case 202: G&0.7P2

1.000 * Load case 1: G
0.700 * Load case 4: P2

Load case 203: G&0.7P3

1.000 * Load case 1: G
0.700 * Load case 5: P3

Load case 204: G&0.7P4

1.000 * Load case 1: G
0.700 * Load case 6: P4

Load case 205: G&0.7P5

1.000 * Load case 1: G
0.700 * Load case 7: P5

Load case 206: G&0.7P6

1.000 * Load case 1: G
0.700 * Load case 8: P6

SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED

Path: C:\Users\Craig\Seajay\Seajay - Documents\Project...\Design\Stairs only

Designer: Date: Wednesday, November 22, 2023 12:29 PM, Page: 2

Filter: No filter

LOAD CASE TITLES

Load Case	Title
1	G
2	Q
3	P1
4	P2
5	P3
6	P4
7	P5
8	P6
9	B1
10	1kN Vibration Check
100	1.2G&1.5Q
101	1.2G&1.5P1
102	1.2G&1.5P2
103	1.2G&1.5P3
104	1.2G&1.5P4
105	1.2G&1.5P5
106	1.2G&1.5P6
200	G&0.7Q
201	G&0.7P1
202	G&0.7P2
203	G&0.7P3
204	G&0.7P4
205	G&0.7P5
206	G&0.7P6

BC240320
Received by
Kapiti Coast District Council
31/05/2024

CALCULATIONS

Project No.:

Date:

Eng:

Page:

27

Project:

Description:

Seajay C
CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE
42 Michael Road, PO Box 1713, Pāpāramu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
seajay@seajay.co.nz

Portal Frame Loads $\Rightarrow S = 3.38m$

FLOOR: [Beam 69]

$$G = 0.41kR \times 3.38m = 1.35 kN/m$$

$$G_{SID} = 0.25kR \times 3.38m = 0.84 kN/m$$

$$\underline{2.20 kN/m}$$

Use $G = 1.35 kN/m$ Deflection

$G = 2.20 kN/m$ Strength

$$Q = 1.5kR \times 3.38m = 5.07 kN/m$$

Use only R strength
BC240320
Received by
Kapiti Coast District Council
31/05/2024

Roof: [Bm 70] $G = 0.3kR \times 3.38m = 1.01 kN/m$

$$Q = 0.25kR \times 3.38m = 0.84 kN/m$$

Use only R strength

Front Lounge Roof Beam Reactions [Node 66]

Beam $L = 4.30m$

$$S = 3.38m$$

$$A = 4.3 \times 3.38 / 2 = 7.27 m^2$$

$$N_G = 0.3kR \times 7.27 m^2 = 2.20 kN$$

$$N_Q = 0.25kR \times 7.27 m^2 = \underline{1.82 kN}$$


SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED

Path: ...ign\Stairs and central landing with PFC and landing - pin back span

Designer: Date: Thursday, February 1, 2024 1:36 PM, Page: 1



REVISED MODEL TO INCLUDE SUPPORTING STRUCTURE



BC240320
Received by
Kapiti Coast District Council
31/05/2024

Sections:

- 1 150x100x9 RHS
- 2 75 PFC
- 3 203x133 UB 25
- 5 203x133 UB 25
- 6 300x100 Roof Beam
- 7 200 PFC
- 8 300x80 Treads
- 16 100*9 SHS

Materials:

- 1 STEEL
- 2 Hardwood



Viewpoint (-44,21)

4.3 DEFLECTIONS

SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED

Path: C:\Use...\Design\Stairs Fw\SLS Model - Mid Span Outrigger - Full Portal

Designer: Date: Thursday, February 1, 2024 3:18 PM, Page: 1

Envelope of absolute maximums for Load cases 10,200-206

(1) SLS


Max

a) Deflection Check - Stair loads only.

$$\Delta_z = 4.41\text{mm} < 5\text{mm} \text{ OK. } (4.48\text{mm with } 100 \times 5 \text{ SHS})$$

Outrigger $\therefore$ OK

$$\frac{h}{\Delta_z} = \frac{5700}{4.41\text{mm}} = 1292 \text{ OK.}$$



$$\Delta_{\text{land}} = 2.19\text{mm}$$

$$\frac{h}{\Delta_y} = \frac{1200}{2.19} = 547 \text{ OK}$$

1 kN on Landing

$$\Delta_{\text{TOP}_H} = 0.4\text{mm}$$

$$\Delta_{\text{LAND}_V} = 0.36\text{mm} < 1\text{mm} \therefore \text{OK}$$

Viewpoint (54,31), Displacements

BC240320
Received by
Kapiti Coast District Council
31/05/2024

Sections:

- 1 150x100x9 RHS
- 2 75 PFC
- 3 203x133 UB 25
- 5 203x133 UB 25
- 6 300X100 Roof Beam
- 7 200 PFC
- 8 300x80 Treads
- 16 100*9 SHS

Materials:

- 1 STEEL
- 2 Hardwood
- 4 F1

SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED

Path: C:\...\Design\Stairs Final ULS Model - Mid Span Outrigger - Full Portal

Designer: Date: Thursday, February 1, 2024 5:13 PM, Page: 1

Envelope of absolute maximums for Load cases 10,200-206

(1) SLS


■ Max



b) Deflection Check - Stair + Frame Gravity

(Note @ Line loads on frame reduce overall deflections on stair ∴ have been ignored)

$$\Delta_H = 4.53\text{mm} < 5\text{mm} \therefore \text{OK} \quad \frac{L}{\Delta} = \frac{5700}{4.5} = 1260$$



BC240320
Received by
Kapiti Coast District Council
31/05/2024

Landing:

$$\Delta_{yL} = 2.23\text{mm}$$

$$\frac{L}{\Delta_y} = \frac{1200}{2.23} = 538 \therefore \text{OK}$$

$$AKN \text{ landing} = 0.2\text{m} \therefore \text{OK}$$

$$\Delta_{KN} \text{ stair} = 0.25\text{m} \therefore \text{OK}$$

Sections:

- 1 150x100x9 RHS
- 2 75 PFC
- 3 203x133 UB 25
- 5 203x133 UB 25
- 6 300X100 Roof Beam
- 7 200 PFC
- 8 300x80 Treads
- 16 100*9 SHS

Materials:

- 1 STEEL
- 2 Hardwood
- 4 F1 Timber



Viewpoint (26,34), Displacements


c) STAIR CENTRE BEAM & TREAD DEFLECTION

SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED
 Path: C:\...\Design\Stairs Final SLS Model - Mid Span Outrigger - Full Portal
 Designer: Date: Thursday, February 1, 2024 5:23 PM, Page: 1
 Filter: Unnamed Filter

Envelope of absolute maximums for Load cases 10,200-206

(1) SLS
 Max

BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024



$$\Delta_{\text{Beam}} = 1.55\text{mm} \quad \frac{1}{\Delta} \geq 400 : 1.0\text{K}$$

$$\Delta_{\text{Tread}} = 3.33\text{mm} - 1.55\text{mm} = 1.78\text{mm}$$

$$\frac{L_c}{\Delta} = \frac{600}{1.78} = 337 > 300 : 0$$

Sections:

Materials:
 1 STEEL
 2 Hardwood

Sections:
 1 150x100x9 RHS
 2 75 PFC
 8 300x80 Treads

$\Delta_{1\text{KN mid stair}} = 0.60\text{mm} < 1\text{mm}$
 $\Delta_{1\text{KN Landing}} = 0.36\text{mm} < 1\text{mm}$
 Viewpoint (12,31), Displacements

4.4 MEMBER STRENGTH


SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED
 Path: C:\...\Design\Stairs Final ULS Model - Mid Span Outrigger - Full Portal
 Designer: Date: Thursday, February 1, 2024 5:53 PM, Page: 1
 Filter: Unnamed Filter

Envelope of absolute maximums for Load cases 100-106

(2) ULS

Max


Bottom Reaction



BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024



a) 150x100x9 RHS CENTRE BEAM



Viewpoint (0,0), Moments, Shears

Materials: 1 STEEL

Sections:

1 150x100x9 RHS

MemDes Calculations @ 18:01:49 01-02-2024 by CJM

Project : 200 Maungakotukutuku Road

Description : Stair Beam

Segment : S1

Section : 150x100x9.0 RHS Grade 350

Major Axis Bending

Design Action $M_x^* = 3.8$ kNm

User provided value for $\alpha_m = 1.00$

$\alpha_s = 1.01$

$\alpha_m * \alpha_s \geq 1.0$, => Segment Fully Restrained

$M_{bx} = M_{sx} = 64.8$ kNm

Major axis capacity Ratio = $M_x^* / \phi M_{bx}$
= 0.06, ---- OK ----

BC240320
Received by
Kapiti Coast District Council
31/05/2024

Shear Calculations (Unstiffened Web)

Design Action $V_x^* = 6.1$ kN

Nominal Shear Yield capacity $V_w = 499.0$ kN

$\alpha_v = 22.33 \geq 1.0$ => full web shear capacity

$V_u = V_w = 499.0$ kN

Shear capacity ratio = $V_x^* / \phi V_u$
= 0.01, ---- OK ----

Axial Calculations

Design Action $N_d = 10.8$ kN [Comp], $Le_{Axx} = 4.74$ m, $Le_{Ayy} = 2.90$ m
= 1365.0 kN

Major axis buckling : Minor axis buckling : Minimum Capac. $N_{cmin} = 759.6$ kN

Axial buckling capac. Ratio = $N_d / \phi N_{cmin}$
= 0.016, ---- OK ----

Combined Actions Checks

Loading PASSES Cl 8.1.4, => Combined Actions Checks are not required

===== SUMMARY =====

**** U.L.S. Capacity Check Passed, Load Cap. Ratio = 0.06 ---- OK ----

CALCULATIONS

Project No. :

Date:

Eng:

Page:


34

Project:

Description:

Seajay C
 CONSULTING ENGINEERS
 CIVIL • STRUCTURAL • FIRE
 42 Michael Road, PO Box 1713, Paraparaumu 6252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 email@seajay.co.nz

b) 100x100x5 SHS Outrigger



100x100x9 SHS (Initial Section).

From Spacegass:

100x100x9 SHS

$$M^* = 6.4 \text{ kNm}$$

$$V^* = 10.63 \text{ kN}$$

$$N^* = 3.10 \text{ kN}$$

$$\phi M_{sx} = 31 \text{ kNm}$$

$$\phi N_x = 280 \text{ kN}$$

$$\phi N_s = 900 \text{ kN}$$

OK by inspection.

Try 100x100x5 SHS

$$\Delta_y = 1.57 \text{ m} \sim \Delta_{y 100 \times 100 \times 5 \text{ SHS}} = 1.37 \text{ m}$$

∴ Short stiff element OK.

$$\phi M_{sx} = 20 \text{ kNm} > M^* = 6.4 \text{ kNm} \therefore \text{OK}$$

$$\phi V_{sx} = 170 \text{ kN} > V^* = 10.63 \text{ kN} \therefore \text{OK}$$

$$\phi N_{sx} = 570 \text{ kN} > N^* = 3.10 \text{ kN} \therefore \text{OK}$$

Use 100x100x5 SHS Outrigger

CALCULATIONS

Project No.:	Date:	Eng:	Page: 35
Project:			
Description:			

Seajay 
 CONSULTING ENGINEERS
 CIVIL • STRUCTURAL • FIRE
 42 Michael Road, PO Box 1713, Paraparaumu 5252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 craig@seajay.co.nz

Connections:

(i) Outrigger to Stair Beam


$$V^* = 10.3 \text{ kN}$$

6m or greater plate ok by inspection
 M12 or greater bolt ok by inspection

(ii) Outrigger to UB moment connection

Bolts

BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024



$$N^*_{\text{Bolt}} = \frac{6.4 \text{ kN}}{0.14}$$

$$= 45.7 \text{ kN}$$

$$V^* = 10.3 \text{ kN} \text{ (Bottom Bolts ok)}$$

6m Gusset
 Each Side
 5 FWAR ok
 by inspection

Need Min 2 - M12

$$N^* = 1.25 \times 45.7 \text{ kN} / 2$$

$$= 28.5 \text{ kN}$$

Allowing for Prying

AISC
Table

$$\phi N_t = 27 \text{ kN}$$

∴ Use 2 - M16 Bolts.

Weld

6m Fillet Weld around / U Butt

$$N^*_F = 6.4 \text{ kN} / (0.1 - 0.05)$$

$$= 67.3 \text{ kN}$$

AISC
Table

$$\phi V_{FW} = 0.557 \text{ kN/mm} \times 100 = 55.7 \text{ kN} < N^*_F$$

Use U Butt Welds + Fillet weld.

CALCULATIONS

Project No. :

Date:

Eng:

Page:

36

Project:

Description:


Seajay

CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

 42 Michael Road, PO Box 1713, Paraparaumu 5252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 email@seajay.co.nz

Out rigger (Continued)

End Plate



$$M^* = 57.12 \text{ kN} \times 0.040 \text{ m} / 2$$

$$= 1.14 \text{ kNm}$$

Section at Bolts will Govern

$$b_e = 130 \text{ mm} - 2 \times 18 = 94 \text{ mm}$$

$$e_e = \sqrt{\frac{4 M^*}{0.9 A_g f_y}}$$

$$= \sqrt{\frac{4 \times 1.14 \times 10^6}{0.9 \times 250 \text{ MPa} \times 94 \text{ mm}}}$$

$$= 14.6 \text{ mm}$$

Say 15 mm Plate.

BC240320

Received by

Kapiti Coast District Council

31/05/2024

CALCULATIONS

Project No. :

Date:

Eng:

Page: 37

Project:


Description:

Seajay 

CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Road, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
seajay@seajay.co.nz

c) New 200UB support Column.



$$M_{1.2G}^* = 1.15 \text{ kNm}$$

$$M_{1.5G}^* = 1.5 \times 2.7 \text{ kN} \times 1.15 \text{ m} = 4.65 \text{ kNm}$$

$$M_{1.5B}^* = 1.5 \times 0.6 \text{ kN} \times 1.2 \text{ m} = 1.08 \text{ kNm}$$

$$M^* = 6.88 \text{ kNm}$$

$$V_{T \& B}^* = 6.88 \text{ kNm} / 2.5 \text{ m} = 2.75 \text{ kN}$$



Project 200 Maungakotukutuku Road Date 2/02/2024

Description Stair Column

Reference

MemDes/V4.2

Designer CJM Page No 38 of

MemDes Calculations @ 07:48:58 02-02-2024 by CJM

Project : 200 Maungakotukutuku Road

Description : Stair Column

Segment : S1

Section : 200UB25 Grade 300+Major Axis BendingDesign Action $M_x^* = 6.9$ kNm $a_m = 1.89$ $a_s = 0.68$ $a_m * a_s \geq 1.0$, => Segment Fully Restrained $M_{bx} = M_{sx} = 82.9$ kNmMajor axis capacity Ratio = $M_x^* / \phi M_{bx}$
= 0.09, ---- OK ----

BC240320
Received by
Kapiti Coast District Council
31/05/2024

Shear Calculations (Unstiffened Web)Design Action $V_x^* = 2.8$ kNNominal Shear Yield capacity $V_w = 226.1$ kN $a_v = 5.03 \geq 1.0$ => full web shear capacity $V_u = V_w = 226.1$ kNShear capacity ratio = $V_x^* / \phi V_u$
= 0.01, ---- OK ----Axial CalculationsDesign Action $N_d = 5.7$ kN [Comp], $Le_{Ax} = 2.50$ m, $Le_{Ay} = 2.50$ m
= 1033.6 kNMajor axis buckling : Minor axis buckling : Minimum Capac. $N_{cmin} = 617.1$ kNAxial buckling capac. Ratio = $N_d / \phi N_{cmin}$
= 0.010, ---- OK ----Combined Actions Checks

Loading PASSES Cl 8.1.4, => Combined Actions Checks are not required

===== SUMMARY =====

**** U.L.S. Capacity Check Passed, Load Cap. Ratio = 0.09 ---- OK ----



Project200.Maungakotukutuku.Road..... Date2/02/2024.....

Description ...Stair.Cantilever.Beam.....

Reference

MemDes/V4.2

DesignerCJM..... Page No 39 of

MemDes Calculations @ 07:50:51 02-02-2024 by CJM

Project : 200 Maungakotukutuku Road

Description : Stair Cantilever Beam

Segment : S1

Section : 150x100x9.0 RHS Grade 350

Major Axis BendingDesign Action $M_x^* = 6.9$ kNm $\alpha_m = 1.89$ $\alpha_s = 1.03$ $\alpha_m * \alpha_s \geq 1.0$, => Segment Fully Restrained $M_{bx} = M_{sx} = 64.8$ kNmMajor axis capacity Ratio = $M_x^* / \phi M_{bx}$
= 0.12, ---- OK ----

BC240320
Received by
Kapiti Coast District Council
31/05/2024

Shear Calculations (Unstiffened Web)Design Action $V_x^* = 2.8$ kNNominal Shear Yield capacity $V_w = 499.0$ kN $\alpha_v = 22.33 \geq 1.0$ => full web shear capacity $V_u = V_w = 499.0$ kNShear capacity ratio = $V_x^* / \phi V_u$
= 0.01, ---- OK ----Axial CalculationsDesign Action $N_d = 3.0$ kN [Comp], $Le_{Ax} = 0.65$ m, $Le_{Ay} = 0.65$ m
= 1365.0 kNMajor axis buckling : Minor axis buckling : Minimum Capac. $N_{e,min} = 1349.9$ kNAxial buckling capac. Ratio = $N_d / \phi N_{e,min}$
= 0.002, ---- OK ----Combined Actions Checks

Loading PASSES Cl 8.1.4, => Combined Actions Checks are not required

===== SUMMARY =====

**** U.L.S. Capacity Check Passed, Load Cap. Ratio = 0.12 ---- OK ----

CALCULATIONS

Project No. :	Date:	Eng:	Page: 40
Project:			
Description:			

Pad:

$$P^* = 5.6 \text{ kN}$$

$$A_b = 5.6 \text{ kN} / 300 \text{ kPa} \times 0.5 \\ = 0.0373 \text{ m}^2 \approx 200 \text{ mm} \square$$

Provide 600 x 600 x 300 Thick.
 Use 650 FD Pad to match front pad.

$$W_1 = 0.6^2 \times 0.3 \times 24 \text{ kN/m}^3 \\ = 4.32 \text{ kN}$$

BC240320

Received by

Kapiti Coast District Council

31/05/2024

$$\therefore 1.2G + 1.5Q$$

$$R^* = 5.6 \text{ kN} + 1.2 \times 4.32 \text{ kN} \\ = 10.8 \text{ kN}$$

$$Q_b^* = 10.8 \text{ kN} / 0.36 \text{ m}^2 = 30 \text{ kPa} < \phi Q = 150 \text{ kPa}$$

$$M_{\text{BASE PLATE}}^* = 10.8 \text{ kN} \times 0.2 \text{ m eccentricity} \\ = 2.16 \text{ kNm}$$

HD BOLTS:

$$N_t^* = \frac{2.16 \text{ kNm}}{0.10 \text{ m}} = 21.6 \text{ kN} / 2 \text{ bolts}$$

2 - M16 bolts ok by inspection

$$\phi N_t = 50 \text{ kN each}$$

Provide 15mm base plate.

Use 650 x 1300 Pad to match front pad. @4PA
 and Utilise bending capacity of base connection.

Pad Footing Design

Job No.: 23020 Date : 5/02/2024
 Project Title : 200 Maungakotukutuku Road, PPM
 Description : New Stair
 Pad No: Post Footing Engineer : CJM

**Pad Geometry:**

Length	0.65 m	Density	24 kN/m ³
Width	1.30 m	Pad Mass	6 kN
Depth underside pad	0.300 m	Pad Modulus	0.18 m ³
Shear Depth	0.200 m (thickness of buried pad)		

Soil Properties:

Bearing Pressure Capacity	qb	300 kPa
Capacity Reduction Factor	ϕ_s	0.5
Hardfill Int. Angle Friction	ϕ	32°
Hardfill Density	γ_s	18 kN/m ³
Base Adhesion	α	0 kPa
Passive Pressure Coeff.	Kp	3.25

Pad Loading:

Utilise Bending Capacity in Post Connection

Over Turning Moment	M*	8 kNm
Axial Load	P*	3.7 kN
Shear	V*	1.75 kN
Load Eccentricity	e	-0.5 m
Base Overturning Moment	M _o	6.675 kNm

Stabilising Actions:

Width Bearing	be	0.09 m
Effective gravity load eccentricity	ef	-0.19
Lever Arm	le	0.79 m
Over Turning Moment	ϕM_o	7 kNm
Sliding	ϕV_o	4 kN

Results:

Reaction Load Eccentricity	0.68 m
Middle Third Reaction	0.22 m
Reaction inside middle third	No
Minimum Bearing Pressure	0.0 kPa
Maximum Bearing Pressure	-311 kPa
Maximum Allow Bearing Pressure	150 kPa
Bearing Length	-0.10 m
Factor of Safety Against Overturning	1.05
Factor of Safety Against Sliding	2.18

CALCULATIONS

Project No. :

Date:

Eng:

Page: 41

Project:

Description:


Seajay C
 CONSULTING ENGINEERS
 CIVIL • STRUCTURAL • FIRE
 42 Michael Road, PO Box 1713, Paraparaumu 5252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 seajay@seajay.co.nz

d) 200PFC Transfer Beam

$$\begin{aligned}
 P_x^* &= 2.25 \text{ kN} \quad \text{Stairs} \\
 &= 2.16 \text{ kN} / 2.5 \\
 &= 0.86 \text{ kN} \quad \text{Induced by footings} \\
 &= 3.61 \text{ kN}
 \end{aligned}$$

$$\begin{aligned}
 M_x^* &= 3.61 \times 3.38 / 4 \\
 &= 3.05 \text{ kNm}
 \end{aligned}$$

$$\begin{aligned}
 V_x^* &= 3.61 / 2 \\
 &= 1.80 \text{ kN}
 \end{aligned}$$



From Spacegass (taking into account torsion).
 BC240320
 Received by
 Kapiti Coast District Council
 31/05/2024

$$M_x^* = 4.9 \text{ kNm}$$

$$M_y^* = 0.55 \text{ kNm}$$

$$V_x^* = 3.91 \text{ kN}$$

Provide 2/M16 Bolts @ each end
 ok strength by inspection.

200PFC Strength ok pgs 42 & 43



Project 200. Maungakotukutuku Road Date 2/02/2024

Description Stair Transfer Beam

Reference

MemDes/V4.2

Designer CJM Page No ~~4~~ 2 ofMemDes Calculations @ 08:27:21 02-02-2024 by CJM

Project : 200 Maungakotukutuku Road

Description : Stair Transfer Beam

Segment : S1

Section : 200PFC Grade 300+Major Axis BendingDesign Action $M_x^* = 5.0$ kNm $\alpha_m = 1.48$ $\alpha_s = 0.50$ $\alpha_m * \alpha_s < 1.0, \Rightarrow$ Segment NOT Fully Restrained $M_{bx} = 1.48 * 0.50 * 66.3 = 48.7$ kNmMajor axis capacity Ratio = $M_x^* / \phi M_{bx}$
= 0.11, ---- OK ----Minor Axis BendingDesign Action $M_y^* = 0.6$ kNm $M_{by} = M_{sy} = 14.01$ kNmMinor axis capacity ratio = $M_y^* / \phi M_{by}$
= 0.04, ---- OK ----

BC240320
Received by
Kapiti Coast District Council
31/05/2024

Shear Calculations (Unstiffened Web)Design Action $V_x^* = 3.6$ kNNominal Shear Yield capacity $V_w = 230.4$ kN $\alpha_v = 5.35 \geq 1.0 \Rightarrow$ full web shear capacity $V_u = V_w = 230.4$ kNShear capacity ratio = $V_x^* / \phi V_u$
= 0.02, ---- OK ----Axial CalculationsDesign Action $N_d = 3.0$ kN [Comp], $L_{eAx} = 3.38$ m, $L_{eAy} = 1.69$ m
= 898.4 kNMajor axis buckling : Minor axis buckling : Minimum Capac. $N_{cmin} = 557.6$ kNAxial buckling capac. Ratio = $N_d / \phi N_{cmin}$
= 0.006, ---- OK ----Combined Actions Checks



Project 200. Maungakotukutuku Road..... Date 2/02/2024.....

Description Stair Transfer Beam.....

Reference

MemDes/V4.2

Designer CJM..... Page No 43 of

Clause 8.3.3/4 :

$$M_{ry} = M_{sy} (1 - (N^*/\phi N_s)) \leq M_{sy} \text{ [Alt. Prov. NOK]}$$

$$= 14.0 \text{ kNm}$$

Clause 8.3.4 : Capac. Ratio = $[N_d/N_s + M^*_x/M_{sx} + M^*_y/M_{sy}]/\phi$

$$= 0.131, \quad \text{---- OK ----}$$

Clause 8.4.2.2 : Major : $M_{ix} = 66.0 \text{ kNm}$

$$\text{Load / Capacity Ratio} = M^*_m/\phi M_i$$

$$= 0.084 \quad \text{---- OK ----}$$

Clause 8.4.2.2 : Minor : $M_{iy} = 13.9 \text{ kNm}$

$$\text{Load / Capacity Ratio} = M^*_m/\phi M_i$$

$$= 0.044 \quad \text{---- OK ----}$$

BC240320
Received by
Kapiti Coast District Council
31/05/2024

Clause 8.4.4.1 :

$$M_{ox} = M_{bx} (1 - N^*/\phi N_{cy}) \leq M_{rx}$$

$$= 48.4 \text{ kNm}$$

$$\text{Load / Capacity Ratio} = M^*_x/\phi M_{ox}$$

$$= 0.115, \quad \text{---- OK ----}$$

Clause 8.4.5.1 :

$$\text{Load / Capacity Ratio} = [M^*_x/\phi M_{ox}]^{1.4} + (M^*_y/\phi M_{oy})^{1.4}$$

$$= 0.061, \quad \text{---- OK ----}$$

===== SUMMARY =====

**** U.L.S. Capacity Check Passed, Load Cap. Ratio = 0.13 ---- OK ----

=====

CALCULATIONS

Project No. :

Date:

Eng:


Page:

44

Project:

Description:

e) Landing Frame



$$M^* = 4.05 \text{ kN} \times 0.6 \text{ m} + 0.9 \text{ kN} \times 1.05 \text{ m}$$

$$= 3.375 \text{ kNm}$$

$$V^* = 4.05 \text{ kN} + 0.9 \text{ kN}$$

$$= 4.95 \text{ kN}$$

BC240320
Received by
Kapiti Coast District Council
31/05/2024

$$l_{ey} = 2 \times 600 \text{ mm} = 1200 \text{ mm}$$

$$\phi M_{bx} = 4.46 \text{ kNm} \quad l_{ey} \leq 1500 \text{ mm} \quad \text{AIS Table}$$

$$\phi V_u = 55 \text{ kN} \quad \therefore \text{OK Strength}$$

f) Stair Tread

300 x 80 Hardwood. (Species to be selected)

Same design actions as PFC above

Hardwood typical SG12 equivalent or better
 $\therefore$ conservatively use SGB

$$f_b = 14.4 \text{ MPa} \quad f_s = 3.8 \text{ MPa} \quad E = 8 \text{ GPa}$$

$$\phi M_b = \phi K_1 K_2 f_b Z$$

Stair loads short duration

$$\therefore K_1 = 1.0$$

$$= 0.8 \times 1.0 \times 1.0 \times 14.4 \times 300 \times 80^2 / 6 / 1 \times 10^6$$


$$= 3.68 \text{ kNm} > M^* = 3.375 \text{ kNm} \quad \therefore \text{OK Strength}$$

CALCULATIONS

Project No.:	Date:	Eng:	Page: 45
Project:			
Description:			

f) Stair Tread (cont)

Stair Tread Fixings & Plate.



Received by
Kapiti Coast District Council
31/05/2024

Two Screws:

$$N_{\text{screw}}^* = 3.375 \text{ kNm} / 0.25 \text{ m} / 2 \text{ Screws} = 6.75 \text{ kN}$$

Four Screws:

$$N_{\text{screw}}^* = 3.375 \text{ kNm} / 0.20 \text{ m} / 4 \text{ Screws} = 4.21 \text{ kN}$$

10 Gauge 4.83φ Screws. min 60mm penetrati-

$$\phi Q_n = \phi n K_1 K_{\text{green}} K_{\text{end}} p Q_k \quad [\text{Eq 4.9 NZS 3603}]$$

$$\phi = 0.7$$

$$n = 1$$

$$K_1 = 1.0 \quad \text{Short term load}$$

$$K_{\text{green}} = 1.0 \quad \text{Dry \& K_{end} = 1.0 \quad \text{Not in end grain}}$$

$$p = 60 \text{ mm} \quad Q_k = 61.7 \text{ N/mm}$$

$$\phi Q_n = 0.7 \times 1 \times 1 \times 1 \times 60 \times 61.7 \text{ N/mm} = 2.59 \text{ kN} \therefore \text{NG}$$

CALCULATIONS

Project No. :

Date:

Eng:

Page:

46

Project:

Description:

Try 14 Gauge 6.3 Ø Screw

$$Q_{K \max} = 5.44 \text{ kN}$$

$$\phi Q_K = 0.7 \times 5.44 \text{ kN} = 3.8 \text{ kN} < Q^* = 4.21 \text{ kN} \therefore \text{NG}$$

$$\therefore \text{Need min} = 6.75 \text{ kN} \times 2 / 3.8 \text{ kN} = 4 \text{ screws centred } 250 \text{ from edge of support}$$

$$Q_K = 79.5 \text{ N/m}$$

$$\therefore \phi Q_n = 0.7 \times 79.5 \text{ N/m} \times 60 \text{ mm}$$

$$= 3.34 \text{ kN}$$

$$\phi M_u = 3.34 \text{ kN} \times 4 \times 0.25 \text{ m}$$

$$= 3.34 \text{ kNm} < 3.375 \text{ kNm} \therefore \text{NG}$$

If use 75mm Screw will get 65mm penetration

$$\therefore \phi Q_n = 0.7 \times 79.5 \text{ N/m} \times 65 \text{ mm} = 3.617 \text{ kN}$$

$$\phi M_u = 3.617 \text{ kN} \times 4 \text{ screws} \times 0.25 \text{ m} = 3.617 \text{ kNm} > 3.375 \text{ kNm} \therefore \text{OK}$$


Steel Plate

$$N^*_{\text{screws}} = 4 \times 3.617 \text{ kN} = 14.4 \text{ kN}$$

$$\therefore M^*_p = 14.4 \text{ kN} \times 0.15 \text{ m} = 2.16 \text{ kNm}$$

$$t_p = \sqrt{\frac{4 M^*_p}{0.9 f_y b_e}} = \sqrt{\frac{4 \times 2.16 \times 10^6}{0.9 \times 250 \times 200}}$$

$$= 13.8 \text{ mm} > 10 \text{ mm Plate} \therefore \text{NG}$$



(Cont Pg 47)

CALCULATIONS

Project No. :

Date:

Eng:

Page:

47

Project:

Description:

Seajay 
CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE
 42 Michael Road, PO Box 1713, Paraparaumu 5252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 craig@seajay.co.nz

Use 6mm Plate & Provide 6mm Stiffener




Plate Thickness : $b_e = 80\text{mm}$ (2x edge dist).

$$N^* = 3.62\text{ kN}$$

$$M^* = 3.62\text{ kN} \times 0.057\text{m} / 2$$

$$= 0.103\text{ kNm}$$

$$f_p = \sqrt{\frac{4 M^*}{0.9 f_y b_e}}$$

$$= \sqrt{\frac{4 \times 0.103 \times 10^6}{0.9 \times 250 \times 80\text{mm}}}$$

$$= 4.78\text{ mm}$$

Use 6mm Plate. Section Remains Elastic.

Tee Section :


$$\phi M_u = 3.80\text{ kNm} > M^* = 2.16\text{ kNm} \therefore \text{OK}$$

48

Stair Tread Bracket			
Design in Accordance with Section 5.0 - NZS 3404:1997 Steel Structures Standard			
Section Properties: (To analyse a plate set flange dimensions to zero)			
Flange Width	200 mm	P.N.A	5.90 mm
Flange Thickness	10 mm	E.N.A (Must be in ste	10.34 mm
Stem Depth	60 mm	Ix	498,409 mm ⁴
Stem Thickness	6 mm	Zx (Flange)	48,207 mm ³
Flange Area	2000 mm ²	Zx (Stem)	8,354 mm ³
Stem Area	360 mm ²	Sx	17,438 mm ³
Overall Depth	70 mm	Iy	6,667,747 mm ⁴
Section Area A	2360 mm ²	J	70,987 mm ³
Section Slenderness: CL 5.2.2			
Member Type	HR (SR,HR,LW,CF,HW)		
Flange λ_{ef}	9.7	Stem λ_{ew}	10
FL Elastic Limit λ_{ey}	16	FL Elastic Limit λ_{ey}	25
FL Plastic Limit λ_{ep}	9	FL Plastic Limit λ_{ep}	9
Flange Must Be Compact	Non Compact Stem		
Zex (Flange)	17438 mm ³	Zex (Stem)	16870 mm ³
Material Properties:			
Yield Strength f_y	250 MPa	Elastic Modulus E	200000 Mpa
Shear Modulus G	80000 MPa		
Member Capacity: CL 5.6			
Section Capacity	$\phi M_s = 0.9 f_y Z_{ex}$	Flange	3.9 kNm
	$\phi M_s = 0.9 f_y Z_{ex}$	Stem	3.80 kNm
Member Length			300 mm
Length Coeff. ΣK_e			1.00
Effective Length			300 mm
Buckling Moment	$M_{oa} = \pi \sqrt{(E I_y G J) / L_e} \cdot \sqrt{1 + k^2}$		911 kNm
	$k = \sqrt{(\pi^2 E I_w / G J L_e^2)}$	$I_w = 0$	
Moment Mod. Factor	α_m (To be assigned)		1.00
Slenderness Factor	$\alpha_s = 0.6 \{ \sqrt{[(M_{sx} / M_{oa})^2 + 3]} - (M_{sx} / M_{oa}) \}$		1.00
Design Actions:			
M^* Flange in Comp	2.16 kNm		
$\phi \cdot M_{bx}$	3.92 kNm		
M^* Stem in Comp	2.16 kNm	Stem in Compression	
$\phi \cdot M_{bx}$	3.80 kNm	OK	
V^*	14.40 kN		
$\phi \cdot V_v = 0.9 \cdot 0.6 f_y A_w$	57 kN	OK	

BC240320
Received by
Kapiti Coast District Council
31/05/2024

5.0 EXISTING STRUCTURE TO SUPPORT STAIRS



BC240320
Received by
Kapiti Coast District Council
31/05/2024



Viewpoint (43,30)

Materials:

- 1 STEEL
- 4 F1 Timber

Sections:

- 3 203x133 UB 25
- 5 203x133 UB 25
- 6 300X100 Roof Beam
- 7 200 PFC

SPACE GASS 14.11 - SEAJAY CONSULTING ENGINEERS LIMITED

Path: C:\...\Design\Stairs Final ULS Model - Mid Span Outrigger - Full Portal

Designer: Date: Friday, February 2, 2024 10:29 AM, Page: 1


Filter: Unnamed Filter

Envelope of absolute maximums for Load cases 100-106

(2) ULS

■ Max

BASE REACTIONS



BC240320
Received by
Kapiti Coast District Council
31/05/2024



Viewpoint (45,26), Reactions

Materials:

■ 1 STEEL

■ 4 F1 Timber

Sections:

■ 3 203x133 UB 25

■ 5 203x133 UB 25

■ 6 300X100 Roof Beam

■ 7 200 PFC

CALCULATIONS

Project No. :

Date:

Eng:

Page:

54

Project:

Description:

Seajay 

CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Road, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

Portal Strength

Design Action:

Column

Beam

Size

200UB2

200UB25

 M^* TOP/End $P_y .50$

14.9 kNm

21.5 kNm

 M^* BOT/MID $P_y .50$

0 kNm

12.2 kNm

Effective Length

2.5m

4.6m
Conservative.
(leg = 1.2m p.p.c.) V^*

BC240320

Received by

Kapiti Coast District Council

31/05/2024

6.0 kN

26.3 kN

 N^*

47.6 kN Comp.

3.9 kN Tension

SR =

0.36 < 1.0

0.39 < 1.0

∴ OK

∴ OK

 $P_y .50$ $P_y .50$ BOLTED JOINT STRENGTH Refe $P_y .50$.

$$\phi M_b = 62 \text{ kNm} \times 249 \text{ kN} / 259 \text{ kN}$$

$$= 60 \text{ kNm} > M^* = 21 \text{ kNm} \quad \therefore$$



Project 200 Maungakotukutuku Road Date 2/02/2024

Description .. Exiting Portals - Portal 1 Column

Reference

MemDes/V4.2

Designer CJM Page No. 55 of

MemDes Calculations @ 10:46:47 02-02-2024 by CJM

Project : 200 Maungakotukutuku Road

Description : Exiting Portals - Portal 1 Column

Segment : S1

Section : 200UB25 Grade 250Major Axis BendingDesign Action $M_x^* = 14.9$ kNmUser provided value for $a_m = 1.00$ ← conservative. → PP Fixity . $a_s = 0.74$ $a_m * a_s < 1.0$, => Segment NOT Fully Restrained $M_{bx} = 1.00 * 0.74 * 67.6 = 49.8$ kNmMajor axis capacity Ratio = $M_x^* / \phi M_{bx}$
= 0.33, ---- OK ----Shear Calculations (Unstiffened Web)Design Action $V_x^* = 6.0$ kNNominal Shear Yield capacity $V_w = 184.9$ kN $a_v = 6.28 >= 1.0$ => full web shear capacity $V_u = V_w = 184.9$ kNShear capacity ratio = $V_x^* / \phi V_u$
= 0.04, ---- OK ----

BC240320
Received by
Kapiti Coast District Council
31/05/2024

Axial CalculationsDesign Action $N_d = 47.6$ kN [Comp], $Le_{Axx} = 2.50$ m, $Le_{Ayy} = 2.50$ m
= 839.8 kNMajor axis buckling : Minor axis buckling : Minimum Capac. $N_{cmin} = 558.4$ kNAxial buckling capac. Ratio = $N_d / \phi N_{cmin}$
= 0.095, ---- OK ----Combined Actions Checks

Clause 8.3.3/4 :

 $M_{ry} = M_{sy} (1 - (N^* / \phi N_s)^2) * 1.19$, =< M_{sy} [Alt. Prov. OK]
= 18.1 kNmLoad / Capacity Ratio = $M_x^* / (0.9 M_{rx})$
= 0.24, ---- OK ----



Project 200. Maungakotukutuku Road Date 2/02/2024

Description Exiting Portals - Portal 1 Column

Reference

MemDes/V4.2

Designer CJM Page No 56 ofClause 8.4.2.2 : Major : $M_{ix} = 63.1 \text{ kNm}$ Load / Capacity Ratio = $M_m^* / \phi M_l$

= 0.262 ---- OK ----

Clause 8.4.4.1 :

 $M_{ox} = M_{bx} (1 - N^* / \phi N_{cy}) \leq M_{rx}$

= 45.1 kNm

Load / Capacity Ratio = $M_x^* / \phi M_{oxr}$

= 0.367, ---- OK ----

===== SUMMARY =====

**** U.L.S. Capacity Check Passed, Load Cap. Ratio = 0.37 ---- OK ----

=====

BC240320
Received by
Kapiti Coast District Council
31/05/2024



Project 200 Maungakotukutuku Road Date 2/02/2024

Description Exiting Portals - Portal 1 Beam

Reference

MemDes/V4.2

Designer CJM Page No 57 of

MemDes Calculations @ 10:52:31 02-02-2024 by CJM

Project : 200 Maungakotukutuku Road

Description : Exiting Portals - Portal 1 Beam

Segment : S1

Section : 200UB25 Grade 250

d = 203 mm b = 133 mm t_f = 7.8 mm t_w = 5.8 mmArea = 3230 mm² f_{yf} = 260 MPa f_{yw} = 260 MPa f_u = 410 MPaI_{xx} = 23.60 E⁶mm⁴ S_x = 260.00 E³mm³ Z_x = 232.00 E³mm³ r_x = 85.40 mmI_{yy} = 3.10 E⁶mm⁴ S_y = 71.40 E³mm³ Z_y = 46.40 E³mm³ r_y = 31.00 mmI_w = 29.50 E⁹mm⁶ J = 61.20 E³mm⁴ k_f = 1.000 Manufact. Type = HR

Compactness(x,y) = C, C

Z_{ex} = 260.00 E³mm³ Z_{ey} = 69.70 E³mm³Member Effective Length Calcs

Torsional End Restraint Conds (TERC) are given as FF

$$\Rightarrow k_t = 1.00$$

User provided value of k_t = 1.40

→ JOIST SIT ON TOP FLANGE

User provided value of k_r = 1.00

$$\text{Eff. Len } L_e = L * k_t * k_l * k_r = 4.60 * 1.00 * 1.40 * 1.00 = 6.44 \text{ m}$$

Major Axis BendingDesign Action M_x^{*} = 21.5 kNmSection Bending Capacity M_{sx} = f_{yf} Z_{ex} = 67.60 kNm

$$\alpha_m = 1.7 * M_m^* / [(M_2^*)^2 + (M_3^*)^2 + (M_4^*)^2]^{0.5} \quad [\text{Eq 5.6.1.1(2)}]$$

$$= 1.7 * 21.0 / [(-2.0)^2 + (12.0)^2 + (2.0)^2]^{0.5} = 2.500$$

Reference Buckling Moment Calculation : M_b

$$\text{Temp. variable } \Pi_2_E_Le2 = \pi^2 * E / L_e^2 = 3.142^2 * 205 \text{ E}6 / 6.440^2 = 48.8 \text{ E}06$$

$$M_b = [(\Pi_2_E_Le2 * I_y) * (G J + (\Pi_2_E_Le2 * I_w))]^{0.5}$$

$$M_b = 31.0 \text{ kNm} \quad (\text{Eqn 5.6.1.1(4)})$$


$$\alpha_s = 0.6 * [((M_s/M_b)^2 + 3)^{0.5} - (M_s/M_b)] = 0.36 \quad [(M_s/M_b) = 67.6 / 31.0 = 2.184]$$

α_m * α_s < 1.0, => Segment NOT Fully Restrained

$$M_{bx} = 2.50 * 0.36 * 67.6 = 61.2 \text{ kNm}$$

Major axis capacity Ratio = M_x^{*} / φ M_{bx}

$$= 0.39, \quad \text{---- OK ----}$$

Shear Calculations (Unstiffened Web)Design Action V_x^{*} = 26.3 kN

$$V_w = 0.6 * F_{yw} * d * t_w = 0.6 * 260000 * 0.203 * 0.006$$

BC240320
Received by
Kapiti Coast District Council
31/05/2024



Project 200 Maungakotukutuku Road Date 2/02/2024

Description Exiting Portals - Portal 1 Beam

Reference

MemDes/V4.2

Designer CJM Page No 58 of

Nominal Shear Yield capacity $V_w = 184.9 \text{ kN}$ $\alpha_v = 6.28 \geq 1.0 \Rightarrow$ full web shear capacity $V_u = V_w = 184.9 \text{ kN}$ Mom-Shear Interaction Check : Moment ratio $\leq 0.75 \Rightarrow$ Clause 5.12.2 N/AShear capacity ratio $= V_x^* / \phi V_u$ $= 0.16, \quad \text{---- OK ----}$ Axial CalculationsDesign Action $N_d = 3.9 \text{ kN}$ [Tens], $L_{eAx} = 4.60 \text{ m}$, $L_{eAy} = 4.60 \text{ m}$ Net area of section A_n $= 3230 - 0$ $= 3230 \text{ mm}^2$ Section Tension Capacity $N_t = A_g f_{y, \text{comb}} \leq 0.85 * k_{te} * A_n * f_u$ $= 3.23 \cdot 10^{-3} * 260.0 \leq 0.85 * 1.00 * 3.23 \cdot 10^{-3} * 410$ $= 839.8 \text{ kN}$ Tension capacity Ratio $= N_d / \phi N_t$ $= 0.005, \quad \text{---- OK ----}$ Combined Actions ChecksCl 8.1.1.1 : Have axial load, in conjunction with flexure, $\Rightarrow$ check Cl 8.1.4

Significant Axial Load test (Cl 8.1.4(b)) IS Satisfied ---- OK ----

Loading PASSES Cl 8.1.4, $\Rightarrow$ Combined Actions Checks are not required

===== SUMMARY =====

**** U.L.S. Capacity Check Passed, Load Cap. Ratio = 0.39 ---- OK ----


=====

BC240320
Received by
Kapiti Coast District Council
31/05/2024

Strengthening of Bolted Joints

59

BC240320
Received by
Kapiti Coast District Council
31/05/2024



M25 Bolts ~ strength of section.

- Remove & reinstall existing bolts on
- Remove & replace with M24 Grade 8.8 Bolts

$$M_{\text{max}}^* = 21.5 \text{ kNm} \quad \text{Pg 54.}$$

		M24	1"
Shank Area	A_0	452 mm^2	506 mm^2
Stress Area	A_s	353 mm^2	390 mm^2
Core Area	A_c	324 mm^2	355 mm^2

Grade 4.6 Bolts

ϕN_{tF}	113 kN	<	124.8 kN
ϕV_{Ft}	64.3 kN	<	70.4 kN
ϕV_{Fc}	89.7 kN	<	100.4 kN

Grade 8.8 Bolts

ϕN_t	234 kN	>	124.8 kN
ϕV_{Ft}	133 kN	>	70.4 kN
ϕV_{Fc}	186 kN	>	100.4 kN

Use M24 Grade 8.8 Bolts if existing bolts to be replaced C.O.S

CALCULATIONS

Project No. :

Date:

Eng:

Page: 61

Project:

Description:

Existing Footing Portal (2) Column.

$N^* = 50 \text{ kN}$ from Spacegaze

$$b = 2'6" \square$$

$$= 760 \square$$

$$\phi Q_b \sim 0.5 \times 300 \text{ kPa} \times 0.76^2$$

$$= 86.6 \text{ kN} > N^* = 50 \text{ kN} \therefore \text{ok}$$

Pad $\#4 \text{ bars @ } 6" \text{ Crs}$
 $= 1/2" \text{ bars @ } 120 \text{ cfs}$

$d = 9" = 228 \text{ mm}$ thick

$$M^*_{\text{pad}} = (50 \text{ kN} / 4 \times 0.76 / 4) / 0.76 \text{ m}$$

$$= 3.12 \text{ kNm/m}$$

2 way Action

$$V^* = 50 \text{ kN} / 4 / 0.76 \text{ m}$$

$$= 16.4 \text{ kN/m}$$

228 pad D12 - 150.

$$\phi M_u = 26.7 \text{ kNm/m} > M^* = 3.12 \text{ kNm/m} \therefore \text{ok}$$

$$\phi U_u = 98.0 \text{ kN/m} > V^* = 16.4 \text{ kN/m} \therefore \text{ok}$$

Existing Pad footing ok.

62

CONCRETE SLABS AND WALLS

(Capacities shown are per metre width of slab)

General Parameters

Type		Slab on Grade	
Depth	D	228 mm	
Concrete Cover To Outside of Reinf. Bars		50 mm	
Concrete Compressive Strength	f'_c or f_m	20 MPa	
Material Type		Concrete	

Shear Capacity

Capacity Reduction Factor	ϕ	0.75
Concrete Shear Stress	$vc = 0.17\sqrt{f'_c}$ or $0.8V_{bm}$ or v_b	0.76 MPa

Shear Capacity	$\phi V_u = \phi \cdot vc \cdot d \cdot B$	98.07 kN
-----------------------	--	-----------------

Flexural Capacity**Reinforcement**

Nomination		D12	
Bar Diameter	d_b	12 (mm)	
Bar Spacing	s	180 (mm)	
Reinforcement Area	A_s	628 (mm ²)	
Steel Yield Strength	f_y	300 (MPa)	
Reinforcement Ratio	μ	0.0037	

Adjusted $\rightarrow$ (150) (250MPa)

Ultimate Moment Capacity

Capacity Reduction Factor	ϕ	0.85 Flexure only
Steel Tension	$T = A_s \cdot f_y$	188 (kN)
Compression Stress Block Depth	$a = T / (0.85 f'_c \cdot B)$	11 (mm)
Depth to Steel	d	172 (mm)

Ultimate Moment Capacity	$\phi M_u = \phi \cdot T \cdot (d - a/2)$	26.67 (kNm)
---------------------------------	---	--------------------

Cracking Moment

Capacity Reduction Factor	ϕ	0.6 Flexure only
Concrete Rupture Stress	$f_r = 0.6\sqrt{f'_c}$	2.68 MPa
Section Modulus	$Z = BD^2/6$	8.7E+6 (mm ³)

Cracking Moment Capacity	$\phi M_{cr} = \phi \cdot f_r \cdot Z$	13.95 (kNm)
---------------------------------	--	--------------------

Minimum Steel**Slabs and Footings (CI 7.3.30 & 8.4.3.4 NZS 3101:1995)**

CI 7.3.30.1	$A_s \min = 0.0014 BD$	319 mm ²
	or $A_s \min = 0.7/f_y BD$	532 mm ²
CI 7.3.30.2	$A_s \min$	1000 mm ²

=> Minimum Steel Required in Slabs & Footings 532 mm² <=

Concrete Walls With Grade 300 Steel (CI 7.3.31.2 NZS 3101:1995)

Minimum Horizontal Steel	$A_s \min = 0.0025 BD$	570 mm ²
Minimum Vertical Steel	$A_s \min = 0.0015 BD$	342 mm ²

Concrete Walls With Mesh or Grade 500 Steel

Minimum Horizontal Steel	$A_s \min = 0.0020 BD$	456 mm ²
Minimum Vertical Steel	$A_s \min = 0.0012 BD$	274 mm ²

Masonry Walls (CI 10.3.4.1 NZS 4230:1990)

Minimum Hori. and Vert. Steel	$A_s \min = 0.0007 BD$	160 mm ²
Minimum Total Steel	$A_s \min = 0.0020 BD$	456 mm ²


Maximum Steel

Balanced Steel Ratio	$\rho_b = \frac{0.85 f'_c \beta_1 \epsilon_s}{f_y (\epsilon_s + f_y)}$	0.0321
	$\beta_1 =$	0.85
	$E_s =$	200000 MPa

Maximum Steel	$A_s \max = 0.75 \rho_b B d$	4142 mm²
----------------------	------------------------------	----------------------------

6.0 BALUSTRADES

6.1 STAIR BALUSTRADE GEOMETRY




BC240320
Received by
Kapiti Coast District Council
31/05/2024

6.2 1st FLOOR WALKWAY BALUSTRADE GEOMETRY

BC240320
Received by
Kapiti Coast District Council
31/05/2024

TOP RAIL span 3.380m



CALCULATIONS

Project No. : Date: Eng: Page: 65

Project:

Description:

Seajay 

CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Road, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

6.3 Balustrade loadings

Use loadcase 1.5①

ULS

①

SLS

Deflection limits

$$\frac{H}{60} + \frac{L}{240}$$

Post

Top Rail.

TABLE 3.3

MINIMUM IMPOSED ACTIONS FOR BARRIERS

		Top edge			Infill		
Type of occupancy for part of the building or structure	Specific uses	Horizontal	Vertical	Inwards, outwards or downwards	Horizontal	Any direction (see Note 2)	
		kN/m	kN/m	kN	kPa	kN	
A	Domestic and residential activities	0.35	0.35	0.6	0.5	0.25	

Note 2: Infill Point Load on any two balusters.

6.4 Infill Design (stair & landing)

$$h_{max} = 870 \text{ mm}$$

$$S_{max} = 110 \text{ mm}$$

(98 gap < 100 mm ok).
Target 90 gap.

$$W^* = 0.5 \text{ kPa} \times 1.5 \times 0.11 \text{ m} \times 0.87 = 0.071 \text{ kN}$$

$$P^* = 0.25 \text{ kN/2} \times 1.5 = 0.188 \text{ kN}$$

$\therefore P^*$ governs.

CALCULATIONS

Project No. :	Date:	Eng:	Page: 66
Project:			
Description:			

6.4 Infill Design (Cont)

$$M^* = \frac{qL}{4} = 0.188 \text{ kN} \times 0.87 / 4$$

$$= 0.041 \text{ kNm}$$

$$V^* = 0.188 \text{ kN} \quad (\text{Point load Top or Bot})$$

Try 12 ϕ Steel Tube.

(12.7 ϕ x 1.6m Thick)

$$Z = 138 \text{ mm}^3$$

$$A = 55 \text{ m}^2$$

$$S = 198 \text{ mm}^3$$

$$I = 877 \text{ mm}^4$$

$$f_y = 275 \text{ MPa}$$

BC240320

Received by

Kapiti Coast District Council

31/05/2024

$$\phi M_u = 0.9 \times 275 \text{ MPa} \times 198 \text{ mm}^3 / 1 \times 10^6$$

$$= 0.049 \text{ kNm} > M^* = 0.041 \text{ kNm} \therefore \text{ok}$$

$$\phi V_u = 0.9 f_y 0.36 A_g$$

$$= 0.9 \times 275 \text{ MPa} \times 0.36 \times 55 \text{ m}^2 / 1000$$

$$= 4.9 \text{ kN} > V^* = 0.188 \text{ kN} \therefore \text{ok}$$

$$\Delta = \frac{188 \text{ N} \times 870^3}{48 \times 200000 \times 877}$$

$$= 14.7 \text{ mm} \approx \frac{h}{5} = 60 \therefore \text{ok}$$

Use 12.7m ϕ x 1.6 wall Steel Tube.

CALCULATIONS

Project No. :	Date:	Eng:	Page: 67
Project:			
Description:			

6.5 Top & Bottom Infill Rail.

$$L_{max} = 1160 \text{ mm}$$

$$S = \frac{870}{2} = 435 \text{ mm}$$

$$W_{\phi}^* = 1.5 \times 0.5 \text{ kN} \times 1.16 \times 0.435 \text{ m} = 0.379 \text{ kN}$$

$$P^* = 1.5 \times 0.25 \text{ kN} = 0.375 \text{ kN}$$

Point Load will Govern by inspection.

$$M^* = 0.375 \text{ kN} \times 1.16 \text{ m} / 4 = 0.108 \text{ kNm}$$

$$V^* = 0.375 \text{ kN}$$

40 wide flat. $d = 40 \text{ mm}$

$$\begin{aligned} t &= 4 \times M^* / 0.9 f_y d^2 \\ &= 4 \times 0.108 \times 10^6 / 0.9 \times 250 \text{ MPa} \times 40^2 \\ &= 1.2 \text{ mm} \quad \text{Use } 40 \times 5 \text{ mm Flat.} \end{aligned}$$

$$\begin{aligned} \phi M_u &= 0.9 \times 250 \text{ MPa} \times 5 \times 40^3 / 4 \\ &= 0.45 \text{ kNm} > 0.108 \text{ kNm} \quad \therefore \text{ok} \end{aligned}$$

$$\Delta = \frac{250 \text{ N} \times 1160^3}{48 \times 200000 \times 5 \times 40^3 / 12}$$

$$= 1.52 \text{ mm} \quad \equiv \frac{L}{\Delta} = \frac{1160}{1.52} = 760 > 240 \therefore \text{ok}$$

CALCULATIONS

Project No. :

Date:

Eng:

Page: 68

Project:

Description:

Seajay 
CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE
 42 Michael Road, PO Box 1713, Paraparaumu 5252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 craig@seajay.co.nz

6.6 Top Rail

$$W_H^* = 0.35 \text{ kN/L} \times 1.5 = 0.52 \text{ kN/L}$$

$$W_V = 0.35 \text{ kN/L} \times 1.5 = 0.52 \text{ kN/L}$$

$$P = 0.6 \text{ kN} \times 1.5 = 0.90 \text{ kN}$$

a) Walkway

$$L = 3.38 \text{ m}$$

$$M_Q^* = 0.52 \text{ kN/L} \times 3.38^2 / 8 = 0.74 \text{ kNm}$$

$$M_P^* = 0.52 \text{ kN/L} \times 3.38 / 4 = 0.76 \text{ kNm}$$

$$V_Q^* = 0.52 \text{ kN/L} \times 3.38 / 2 = 0.87 \text{ kN}$$

$$V_P^* = 0.90 \text{ kN}$$

50 x 25 x 3 RHS on Flat

$$A_g = 391 \text{ mm}^2$$

$$I_x = 112000 \text{ mm}^4$$

$$S_x = 5860 \text{ mm}^3$$

$$f_y = 350 \text{ MPa}$$

$$I_y = 36700 \text{ mm}^4$$

$$S_y = 3560 \text{ mm}^3$$

$$\phi M_u = 0.9 f_y S_x$$

$$= 0.9 \times 350 \text{ MPa} \times 5860 \text{ mm}^3 / 1 \times 10^6$$

$$= 1.84 \text{ kNm} > M^* = 0.76 \text{ kNm} \therefore \text{OK}$$

Shear OK by inspection

CALCULATIONS

Project No. :

Date:

Eng:

Page: 69

Project:

Description:

Seajay 
 CONSULTING ENGINEERS
 CIVIL • STRUCTURAL • FIRE
 42 Michael Road, PO Box 1713, Paraparaumu 5252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 craig@seajay.co.nz

6.6 Top Rail (Cont) 50 x 25 x 3 RHS

$$\Delta = \frac{600N \times 3380^3}{48 \times 200000 \times 112000 \text{ mm}^4}$$

$$= 21 \text{ mm} \quad \Rightarrow \quad \frac{L}{\Delta} = 160 < 240 \quad \therefore \text{OK}$$

Try 75 x 25 x 2.5 RHS

$$\Delta = \frac{600 \times 3380^3}{48 \times 200000 \times 235000 \text{ mm}^4}$$

$$= 8.25 \text{ mm} \quad \Rightarrow \quad \frac{L}{\Delta} = 409 > 240 \quad \therefore \text{OK}$$

BC240320

Received by

Kapiti Coast District Council

31/05/2024

Check Top Rail for Stairs

50 x 25 x 2.5 RHS

$$L = 840 \times 2$$


$$= 1680 \text{ mm} \quad \text{to Spread Point load between 3 posts}$$

$$\Delta = \frac{600N \times 1680^3}{48 \times 200000 \times 98900 \text{ mm}^4}$$

$$= 3.0 \text{ mm} \quad \therefore \text{OK}$$

Use: 75 x 25 x 2.5 RHS Landing Top Rail

50 x 25 x 2.5 RHS Stair Top Rail
(to meet grip requirement.)



= 75mm OK

CALCULATIONS

Project No. :

Date:

Eng:

Page:

70

Project:

Description:

Seajay 


CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Road, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

67 Posts

Stair Govers as posts on landing
span Floor - Top Rail. From Pg 68
Point load Govers

$$S = 840\text{mm}$$



Design Actions:

$$M_{\text{post}}^* = 0.9\text{ kN} \times 1.144\text{ m} = 1.03\text{ kNm}$$

$$V_{\text{post}}^* = 0.9\text{ kN}$$

CALCULATIONS

Project No. :	Date:	Eng:	Page: 71
Project:			
Description:			

40 x 40 x 3 SHS Posts

$$\phi M_u = 0.9 f_y S_x$$

$$S_x = 5720 \text{ cm}^3$$

$$= 6740 \text{ cm}^3$$

3mm Thick

4mm Thick.

$$\therefore \phi M_u = 0.9 \times 350 \text{ MPa} \times 5720 \text{ cm}^3 / 1 \times 10^6$$

$$= 1.80 \text{ kNm} > M^* = 1.03 \text{ kNm} \therefore \text{OK.}$$

Top Rail will spread load to adjacent Posts.

BC240320

Received by

Kapiti Coast District Council

31/05/2024

Deflection

$$\Delta = \frac{PL^3}{3EI}$$

$$P_{sls} = 600 \text{ N} / 2 \text{ Posts}$$

$$= 300 \text{ N}$$

$$P_{sls} = 0.360 \text{ kN/m} \times 0.84 \text{ m} \times 1000$$

$$= 302 \text{ N}$$

$$\Delta = \frac{302 \times 1144^3}{3 \times 200000 \times 93200 \text{ cm}^4}$$

$$= 8.08 \text{ mm} = \frac{L}{\Delta} = \frac{1144}{8.08} = 141 > 60$$

$\therefore \text{OK.}$

CALCULATIONS

Project No. :	Date:	Eng:	Page: 72
Project:			
Description:			

Post Connection 14 Gauge 6.30 Screws

$$\phi Q_n = 3.34 \text{ kN} \quad \text{Pg 46.}$$

∴ Two Screws

$$\phi Q = 3.34 \text{ kN} \times 2 = 6.68 \text{ kN.}$$


$$S_{\text{screws}} = \frac{1.03 \text{ kN}}{6.68 \text{ kN}} = 0.154 \text{ m}$$

BC240320

Received by

Kapiti Coast District Council

31/05/2024



Check Vertical Load.

$$P^* = 0.9 \text{ kN}$$

$$Q^* = 0.9 \text{ kN} \times (150 + 60 + 10 + \frac{40}{2}) / 150 = 1.44 \text{ kN} < \phi Q_n = 6.68 \text{ kN} \therefore \text{OK}$$

Post to 75 PFC

2-M10 Bolts.

$$N_{\text{bolt}}^* = 1.03 \text{ kN} / (0.075 \text{ m} / 2) / 2 \text{ bolts} = 13.7 \text{ kN.}$$

$$\phi N_t = 0.8 \times 23.2 \text{ kN} = 18.5 \text{ kN} > N^* = 13.7 \text{ kN} \therefore \text{OK}$$

$$\phi V_{fn} = 10.4 \text{ kN} > V^* = 0.9 \text{ kN} \therefore \text{OK}$$

CALCULATIONS

Project No. :

Date:

Eng:

Page:


73

Project:

Description:

Seajay 
CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE
 42 Michael Road, PO Box 1713, Paraparaumu 5252
 Phone: (04) 212 5150 • Cell: 021 121 4591
 craig@seajay.co.nz

Nominal Fixings To Timber Floor.



$$\phi M_u = 6.68\text{kN} \times 0.1\text{m}$$

$$= 0.668\text{kNm}$$

OK ~ 2/3 Moment

4/14G Screws

$$\phi Q_{sk} = 0.7 \times k_1 \times k_g \times k_e \times Q_{sk}$$

$$= 0.7 \times 1.0 \times 1.0 \times 1.0 \times 2.663 \times 2$$

$$= 3.7\text{kN} > V^* = 0.38\text{kN} \therefore \text{OK}$$

BC210320

Received by

Kapiti Coast District Council

31/05/2024



association of
consulting and
engineering



PRODUCER STATEMENT – PS4 CONSTRUCTION REVIEW

BUILDING CODE CLAUSE(S): B1

JOB NUMBER: 23020

ISSUED BY: Seajay Consulting Engineers Ltd
(Construction Monitoring Firm)

TO: Peter Saunders
(Owner/Developer)

TO BE SUPPLIED TO: Kapiti Coast District Council
(Building Consent Authority)

IN RESPECT OF: New Internal Stairs
(Description of Building Work)

AT: 200 Maungakotukutuku Road, Paraparaumu
(Address, Town/City)

LEGAL DESCRIPTION: Lot 20 DP 33688

N/A ☐

We have been engaged by the owner/developer referred to above to provide CM 3 level of construction monitoring relating to the Clause(s) named above of the Building Code for the building work which is covered by PS1(s) issued by Seajay Consulting Engineers Limited (Engineering Design Firm) and which is described in the documents relating to the Building Consent No. BC 240320 and those relating to Building Consent Amendment(s) No. Nil issued during the course of the works.

We have sighted these Building Consents and the conditions attached to them.
If any of the fields above are too small, please write "refer the Schedule".

Authorised instructions/variation(s) detailed/listed in the Schedule have been issued during the course of the works.

On the basis of these review(s) and information supplied by the contractor during the course of the works and on behalf of the engineering firm undertaking this Construction Monitoring, I believe on reasonable grounds that the building works covered by the above-mentioned PS1(s) have been completed in accordance with the relevant requirements of the Building Consent and Building Consent Amendments identified above or in the Schedule on page 2, with respect to Clause(s) B1/VM1 & VM4 of the Building Code. I also believe on reasonable grounds that the persons who have undertaken this construction review have the necessary competency to do so.

I, (Name of Construction Monitoring Professional) Craig McGhie, am:
• CPEng number 173345
• I hold the following qualifications NZCE, BE (Civil) Hon, ME (Fire)

The Construction Monitoring Firm holds a current policy of Professional Indemnity Insurance no less than \$200,000. Is

SIGNED BY (Name of Construction Monitoring Professional): Craig McGhie
(Signature below):

ON BEHALF OF (Construction Monitoring Firm): Seajay Consulting Engineers Ltd

Date: 10/1/25

Note: This statement has been prepared solely for the Building Consent Authority named above and shall not be relied upon by any other person or entity. Any liability in relation to this statement accrues to the Construction Monitoring Firm only. As a condition of reliance on this statement, the Building Consent Authority accepts that the total maximum amount of liability of any kind arising from this statement and all other statements provided to the Building Consent Authority in relation to this building work, whether in tort or otherwise, is limited to the sum of \$200,000.

This form is to accompany **Forms 6 or 8 of the Building (Forms) Regulations 2004** for the issue of a Code Compliance Certificate.

THIS FORM AND ITS CONDITIONS ARE COPYRIGHT TO ACE NEW ZEALAND AND ENGINEERING NEW ZEALAND

SCHEDULE to PS4

Please include an itemised list of all referenced documents, drawings, or other supporting materials in relation to this producer statement below: |

Site Reports:

23020 - SR01 - Foundations
23020 - SR02 - Steel Structure
23020 - SR03 - Completed stairs

BC240320
Received by
Kapiti Coast District Council
10/03/2025
via Simpli

GUIDANCE ON USE OF PRODUCER STATEMENTS

Information on the use of Producer Statements and Construction Monitoring Guidelines can be found on the Engineering New Zealand website

<https://www.engineeringnz.org/engineer-tools/engineering-documents/producer-statements/>

Producer statements were first introduced with the Building Act 1991. The producer statements were developed by a combined task committee consisting of members of the New Zealand Institute of Architects (NZIA), Institution of Professional Engineers New Zealand (now Engineering New Zealand), Association of Consulting and Engineering New Zealand (ACE NZ) in consultation with the Building Officials Institute of New Zealand (BOINZ). The original suite of producer statements has been revised at the date of this form to ensure standard use within the industry.

The producer statement system is intended to provide Building Consent Authorities (BCAs) with part of the reasonable grounds necessary for the issue of a Building Consent or a Code Compliance Certificate, without necessarily having to duplicate review of design or construction monitoring undertaken by others.

PS1 DESIGN Intended for use by a suitably qualified independent engineering design professional in circumstances where the BCA accepts a producer statement for establishing reasonable grounds to issue a Building Consent;

PS2 DESIGN REVIEW Intended for use by a suitably qualified independent engineering design review professional where the BCA accepts an independent design professional's review as the basis for establishing reasonable grounds to issue a Building Consent;

PS3 CONSTRUCTION Forms commonly used as a certificate of completion of building work are Schedule 6 of NZS 3910:2013 or Schedules E1/E2 of NZIA's SCC 2011²

PS4 CONSTRUCTION REVIEW Intended for use by a suitably qualified independent engineering construction monitoring professional who either undertakes or supervises construction monitoring of the building works where the BCA requests a producer statement prior to issuing a Code Compliance Certificate.

This must be accompanied by a statement of completion of building work (Schedule 6).

The following guidelines are provided by ACE New Zealand and Engineering New Zealand to interpret the Producer Statement.

Competence of Engineering Professional

This statement is made by an engineering firm that has undertaken a contract of services for the services named, and is signed by a person authorised by that firm to verify the processes within the firm and competence of its personnel.

The person signing the Producer Statement on behalf of the engineering firm will have a professional qualification and proven current competence through registration on a national competence-based register such as a Chartered Professional Engineer (CPEng).

Membership of a professional body, such as Engineering New Zealand provides additional assurance of the designer's standing within the profession. If the engineering firm is a member of ACE New Zealand, this provides additional assurance about the standing of the firm.

Persons or firms meeting these criteria satisfy the term "suitably qualified independent engineering professional".

Professional Indemnity Insurance

As part of membership requirements, ACE New Zealand requires all member firms to hold Professional Indemnity Insurance to a minimum level.

The PI Insurance minimum stated on the front of this form reflects standard practice for the relationship between the BCA and the engineering firm.

Professional Services during Construction Phase

There are several levels of service that an engineering firm may provide during the construction phase of a project (CM1-CM5 for engineers³). The building Consent Authority is encouraged to require that the service to be provided by the engineering firm is appropriate for the project concerned.

Requirement to provide Producer Statement PS4

Building Consent Authorities should ensure that the applicant is aware of any requirement for producer statements for the construction phase of building work at the time the building consent is issued as no design professional should be expected to provide a producer statement unless such a requirement forms part of the Design Firm's engagement.

Refer Also:

- 1 Conditions of Contract for Building & Civil Engineering Construction NZS 3910: 2013
- 2 NZIA Standard Conditions of Contract SCC 2011
- 3 Guideline on the Briefing & Engagement for Consulting Engineering Services (ACE New Zealand/Engineering New Zealand 2004)
- 4 PN01 Guidelines on Producer Statements

www.acenz.org.nz
www.engineeringnz.org

BC240320
Received by
Kapiti Coast District Council
10/03/2025
via Simpli

SITE INSPECTION REPORT

Job No.: 23020	Report No.: SRD1
Date: 16/7/2024	Sheet 1 of 1
Project: 200 Maunga Kotukutuku Rd. New Stair	



CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Rd, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

Area Inspected: Footings & Bolts	BC Number:
Inspected by: Craig McGhie	Contractors Rep:

Observations:

- ① 650W x 1300 long x 300 D Footings ok
 - 3/HD12 long - T & B ok
 - HD10 Stirrups - 300 ok
 - HD10 Starters to floor ok

- ② Portal frame bolts replaced with new M24 grade 8-8 bolts ok

80240320
Received by
Kapiti Coast District Council
10/03/2025
via Simpli

Instructions Given:

- ① ok to pour Footings

Next Inspection: Stair Structure

Approved: (Signed:)	Not approved – Hold Point: (Signed:)		
Work may proceed: (Subject to completing above instructions)	Work may not proceed: (Further design/instruction and re-inspection required.)	Re-inspection required (Following completion of above instructions.)	Contractor to supply photographs (For approval following completion of above instructions. Work not to proceed until approval given.)

Note that the above approval does not include statutory inspections and approval which may be required by the Building Consent Authority. Similarly Building Consent Authority approval does not preclude re-inspection or implementation of further instructions directed herewith where the inspection was "Not Approved".

SITE INSPECTION REPORT

Job No.: 23020	Report No.: SROZ
Date: 28/8/2024	Sheet 1 of 2
Project: 200 Maungakotukutuku Road New Stairs	
Area Inspected: Stair Structure.	BC Number:
Inspected by: Craig McChie	Contractors Rep: Peter Saunders



CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Rd, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

Observations:

① Stair structure fabricated in accordance with drawing 23020-S4, S5, S6 & S7.

- 150x100x9 RHS Centre Beam ok
- 6mm steel plates to treads ok
- 75 PFC Landing Frame ok

② Stair Balustrade fabricated in accordance with Detail S & Section F Drawing S7

- 50x25x2.5 RHS Top rail ok
- 40x6 F100 Intermediate & Bottom Rail ok
- 12 Ø ok

BC240320
Received by
Kapiti Coast District Council
10/03/2025
Via Simphi

③ Landing Support column installed as per Section E/S6

- 200UB25 Column ok
- 150x100x9 RHS Outrigger Beam ok
- 200PFC transom beam ok
- Connections as per details. ok

④ Mid Height outrigger beam installed as per Section D/S6

- 100x100x5 SHS outrigger ok
- 6mm Stiffeners to existing 200UB25 Column ok
- M16 Bolts to existing column ok

Next Inspection: Stair Treads

Approved: (Signed:)	Not approved – Hold Point: (Signed:)			
Work may proceed: (Subject to completing above instructions)	Work may not proceed. (Further design/instruction and re-inspection required.)	Re-inspection required (Following completion of above instructions.)	Contractor to supply photographs (For approval following completion of above instructions. Work not to proceed until approval given.)	

Note that the above approval does not include statutory inspections and approval which may be required by the Building Consent Authority. Similarly Building Consent Authority approval does not preclude re-inspection or implementation of further instructions directed herewith where the inspection was "Not Approved".

SITE INSPECTION REPORT

Job No.: 23020	Report No.: SR02
Date:	Sheet 2 of 2
Project: 200 Munga Kotukutuku Rd. New Stairs	
Area Inspected: Stair Structure.	BC Number:
Inspected by: Craig McGhie	Contractors Rep: Peter Saunders



CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Rd, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

Observations:

- ⑤ The landing balustrade has been installed as per the details on drawing S8
- 75x25x2.5 RHS Top Rail. ok
 - 40x6 Flat intermediate & bottom Rail ok
 - 12Ø balusters ok
 - Fixings as per drawings ok

BC240320
Received by
Kapiti Coast District Council
10/03/2025
via Simpli

Instructions Given:

- ① Complete installation of stair treads.
- ② Plywood stair treads (80mm thick) ok.

Next Inspection: Stair treads

Approved: (Signed:)		Not approved – Hold Point: (Signed: Peter to supply photos of installed treads)	
Work may proceed: (Subject to completing above instructions)	Work may not proceed: (Further design/instruction and re-inspection required.)	Re-inspection required (Following completion of above instructions.)	Contractor to supply photographs (For approval following completion of above instructions. Work not to proceed until approval given.)

Note that the above approval does not include statutory inspections and approval which may be required by the Building Consent Authority. Similarly Building Consent Authority approval does not preclude re-inspection or implementation of further instructions directed herewith where the inspection was "Not Approved".

SITE INSPECTION REPORT

Job No.: 23020	Report No.: SR03	Seajay  CONSULTING ENGINEERS CIVIL • STRUCTURAL • FIRE 42 Michael Rd, PO Box 1713 Paraparaumu 5252 Phone: (04) 212 5150 • Cell: 021 121 4591 craig@seajay.co.nz
Date: 10/1/2025	Sheet 1 of 2	
Project: 200 Maungakotukutuku Road Paraparaumu		
Area Inspected: Stair Final		BC Number:
Inspected by: (Photos by Client)		Contractors Rep: Peter Saunders

Observations:

The client has installed 80mm thick plywood treads and landings as per the design drawings.




Photo 1 – Completed Stairs




Photo 2 – Completed stairs and treads

BC240320
Received by
Kapiti Coast District Council
10/03/2025
via Simpli




Photo 3 – Completed landing




Photo 4 – Typical tread installation

Instructions Given:

Nil

Next Inspection:

Approved: (Signed:) 		Not approved – Hold Point: (Signed:)			
Work <u>may</u> proceed: (Subject to completing above instructions)	☒	Work may <u>not</u> proceed. (Further design/instruction and re-inspection required.)	Re-inspection required (Following completion of above instructions.)	Contractor to <u>supply photographs</u> (For approval following completion of above instructions. Work not to proceed until approval given.)	

Note that the above approval does not include statutory inspections and approval which may be required by the Building Consent Authority. Similarly Building Consent Authority approval does not preclude re-inspection or implementation of further instructions directed herewith where the inspection was "Not Approved".

Disclaimer:

This document has been prepared solely for Peter Saunders name. The use of and reliance upon the information or opinions contained in this document by others without prior written consent from Seajay Consulting Engineers will be at such person's sole risk. Seajay Consulting Engineers accepts no responsibility or liability for the consequences of the unauthorised use of this document.

BC240320
 Received by
 Kapiti Coast District Council
 10/03/2025
 via Simpli



association of
consulting and
engineering



PRODUCER STATEMENT – PS4

CONSTRUCTION REVIEW

BUILDING CODE CLAUSE(S): B1

JOB NUMBER: 23020

ISSUED BY: Seajay Consulting Engineers Ltd

(Construction Monitoring Firm)

TO: Peter Saunders

(Owner/Developer)

TO BE SUPPLIED TO: Kapiti Coast District Council

(Building Consent Authority)

IN RESPECT OF: New Internal Stairs

(Description of Building Work)

AT: 200 Maungakotukutuku Road, Paraparaumu

(Address, Town/City)

LEGAL DESCRIPTION: Lot 20 DP 33688

N/A ☐

BC240320
Received by
Kapiti Coast District Council
10/01/25
via email

We have been engaged by the owner/developer referred to above to provide CM 3 **level of construction monitoring** relating to the Clause(s) named above of the Building Code for the building work which is covered by PS1(s) issued by Seajay Consulting Engineers Limited (Engineering Design Firm) and which is described in the documents relating to the Building Consent No. BC 240320 and those relating to Building Consent Amendment(s) No. Nil issued during the course of the works.

We have sighted these Building Consents and the conditions attached to them.
If any of the fields above are too small, please write "refer the Schedule".

Authorised instructions/variation(s) detailed/listed in the Schedule have been issued during the course of the works.

On the basis of these review(s) and information supplied by the contractor during the course of the works and on behalf of the engineering firm undertaking this Construction Monitoring, I believe on reasonable grounds that the building works covered by the above-mentioned PS1(s) have been completed in accordance with the relevant requirements of the Building Consent and Building Consent Amendments identified above or in the Schedule on page 2, with respect to Clause(s) B1/VM1 & VM4 of the Building Code. I also believe on reasonable grounds that the persons who have undertaken this construction review have the necessary competency to do so.

I, (Name of Construction Monitoring Professional) Craig McGhie, am:

- CPEng number 173345
- I hold the following qualifications NZCE, BE (Civil) Hon, ME (Fire)

The Construction Monitoring Firm holds a current policy of Professional Indemnity Insurance no less than \$200,000. Is

SIGNED BY (Name of Construction Monitoring Professional): Craig McGhie
(Signature below):

ON BEHALF OF (Construction Monitoring Firm): Seajay Consulting Engineers Ltd

Date: 10/1/25

Note: This statement has been prepared solely for the Building Consent Authority named above and shall not be relied upon by any other person or entity. Any liability in relation to this statement accrues to the Construction Monitoring Firm only. As a condition of reliance on this statement, the Building Consent Authority accepts that the total maximum amount of liability of any kind arising from this statement and all other statements provided to the Building Consent Authority in relation to this building work, whether in tort or otherwise, is limited to the sum of \$200,000.

This form is to accompany **Forms 6 or 8 of the Building (Forms) Regulations 2004** for the issue of a Code Compliance Certificate.

THIS FORM AND ITS CONDITIONS ARE COPYRIGHT TO ACE NEW ZEALAND AND ENGINEERING NEW ZEALAND

SCHEDULE to PS4

Please include an itemised list of all referenced documents, drawings, or other supporting materials in relation to this producer statement below: |

Site Reports:

23020 - SR01 - Foundations
23020 - SR02 - Steel Structure
23020 - SR03 - Completed stairs

GUIDANCE ON USE OF PRODUCER STATEMENTS

Information on the use of Producer Statements and Construction Monitoring Guidelines can be found on the Engineering New Zealand website

<https://www.engineeringnz.org/engineer-tools/engineering-documents/producer-statements/>

Producer statements were first introduced with the Building Act 1991. The producer statements were developed by a combined task committee consisting of members of the New Zealand Institute of Architects (NZIA), Institution of Professional Engineers New Zealand (now Engineering New Zealand), Association of Consulting and Engineering New Zealand (ACE NZ) in consultation with the Building Officials Institute of New Zealand (BOINZ). The original suite of producer statements has been revised at the date of this form to ensure standard use within the industry.

The producer statement system is intended to provide Building Consent Authorities (BCAs) with part of the reasonable grounds necessary for the issue of a Building Consent or a Code Compliance Certificate, without necessarily having to duplicate review of design or construction monitoring undertaken by others.

PS1 DESIGN Intended for use by a suitably qualified independent engineering design professional in circumstances where the BCA accepts a producer statement for establishing reasonable grounds to issue a Building Consent;

PS2 DESIGN REVIEW Intended for use by a suitably qualified independent engineering design review professional where the BCA accepts an independent design professional's review as the basis for establishing reasonable grounds to issue a Building Consent;

PS3 CONSTRUCTION Forms commonly used as a certificate of completion of building work are Schedule 6 of NZS 3910:2013 or Schedules E1/E2 of NZIA's SCC 2011²

PS4 CONSTRUCTION REVIEW Intended for use by a suitably qualified independent engineering construction monitoring professional who either undertakes or supervises construction monitoring of the building works where the BCA requests a producer statement prior to issuing a Code Compliance Certificate.

This must be accompanied by a statement of completion of building work (Schedule 6).

The following guidelines are provided by ACE New Zealand and Engineering New Zealand to interpret the Producer Statement.

Competence of Engineering Professional

This statement is made by an engineering firm that has undertaken a contract of services for the services named, and is signed by a person authorised by that firm to verify the processes within the firm and competence of its personnel.

The person signing the Producer Statement on behalf of the engineering firm will have a professional qualification and proven current competence through registration on a national competence-based register such as a Chartered Professional Engineer (CPEng).

Membership of a professional body, such as Engineering New Zealand provides additional assurance of the designer's standing within the profession. If the engineering firm is a member of ACE New Zealand, this provides additional assurance about the standing of the firm.

Persons or firms meeting these criteria satisfy the term "suitably qualified independent engineering professional".

Professional Indemnity Insurance

As part of membership requirements, ACE New Zealand requires all member firms to hold Professional Indemnity Insurance to a minimum level.

The PI Insurance minimum stated on the front of this form reflects standard practice for the relationship between the BCA and the engineering firm.

Professional Services during Construction Phase

There are several levels of service that an engineering firm may provide during the construction phase of a project (CM1-CM5 for engineers³). The building Consent Authority is encouraged to require that the service to be provided by the engineering firm is appropriate for the project concerned.

Requirement to provide Producer Statement PS4

Building Consent Authorities should ensure that the applicant is aware of any requirement for producer statements for the construction phase of building work at the time the building consent is issued as no design professional should be expected to provide a producer statement unless such a requirement forms part of the Design Firm's engagement.

Refer Also:

- 1 Conditions of Contract for Building & Civil Engineering Construction NZS 3910: 2013
- 2 NZIA Standard Conditions of Contract SCC 2011
- 3 Guideline on the Briefing & Engagement for Consulting Engineering Services (ACE New Zealand/Engineering New Zealand 2004)
- 4 PN01 Guidelines on Producer Statements

www.acenz.org.nz

www.engineeringnz.org

SITE INSPECTION REPORT

Job No.: 23020	Report No.: SRD1
Date: 16/7/2024	Sheet 1 of 1
Project: 200 Maunga Kotukutuku Rd. New Stair	



CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Rd, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

Area Inspected: Footings & Bolts	BC Number:
Inspected by: Craig McGhie	Contractors Rep:

Observations:

- ① 650W x 1300 long x 300 D Footings OK
 - 3/HD12 long - T & B OK
 - HD10 Stirrups - 300 OK
 - HD10 Starters to floor OK
- ② Portal frame bolts replaced with new M24 grade 8-8 bolts OK

Instructions Given:

- ① OK to pour Footings

Next Inspection: Stair Structure

Approved: (Signed:)	Not approved – Hold Point: (Signed:)		
Work may proceed: (Subject to completing above instructions)	Work may not proceed. (Further design/instruction and re-inspection required.)	Re-inspection required (Following completion of above instructions.)	Contractor to supply photographs (For approval following completion of above instructions. Work not to proceed until approval given.)

Note that the above approval does not include statutory inspections and approval which may be required by the Building Consent Authority. Similarly Building Consent Authority approval does not preclude re-inspection or implementation of further instructions directed herewith where the inspection was "Not Approved".

SITE INSPECTION REPORT

Job No.: 23020	Report No.: SROZ
Date: 28/8/2024	Sheet 1 of 2
Project: 200 Maungakotukutuku Road New Stairs	
Area Inspected: Stair Structure.	BC Number:
Inspected by: Craig McChie	Contractors Rep: Peter Saunders



CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Rd, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

Observations:

① Stair structure fabricated in accordance with drawing 23020-S4, S5, S6 & S7.

- 150x100x9 RHS Centre Beam ok
- 6mm steel plates to treads ok
- 75 PFC landing frame ok

② Stair Balustrade fabricated in accordance with Detail S & Section F Drawing S7

- 50x25x2.5 RHS Top rail ok
- 40x6 Flat intermediate & bottom Rail ok
- 12 Ø balusters ok

③ landing support column installed as per Section E/S6

- 200UB25 column ok
- 150x100x9 RHS Outrigger Beam ok
- 200PFC transom beam ok
- Connections as per details. ok

④ Mid Height outrigger beam installed as per Section D/S6

- 100x100x5 SHS outrigger ok
- 6mm stiffeners to existing 200UB25 column ok
- M16 Bolts to existing column ok

Next Inspection: Stair Treads

Approved: (Signed:)		Not approved – Hold Point: (Signed:)			
Work may proceed: (Subject to completing above instructions)	Work may not proceed. (Further design/instruction and re-inspection required.)	Re-inspection required (Following completion of above instructions.)	Contractor to supply photographs (For approval following completion of above instructions. Work not to proceed until approval given.)		

Note that the above approval does not include statutory inspections and approval which may be required by the Building Consent Authority. Similarly Building Consent Authority approval does not preclude re-inspection or implementation of further instructions directed herewith where the inspection was "Not Approved".

SITE INSPECTION REPORT

Job No.: 23020	Report No.: S202
Date:	Sheet 2 of 2
Project: 200 Maunga Kotukutuku Rd. New Stairs	
Area Inspected: Stair Structure.	BC Number:
Inspected by: Craig McGhie	Contractors Rep: Peter Saunders



CONSULTING ENGINEERS
CIVIL • STRUCTURAL • FIRE

42 Michael Rd, PO Box 1713, Paraparaumu 5252
Phone: (04) 212 5150 • Cell: 021 121 4591
craig@seajay.co.nz

Observations:

- ⑤ The landing balustrade has been installed as per the details on drawing S8
- 75x25x2.5 RHS Top Rail. ok
 - 40x6 Flat intermediate & bottom Rail ok
 - 12Ø balusters ok
 - Fixings as per drawings ok

Instructions Given:

- ① Complete installation of stair treads.
- ② Plywood stair treads (80mm thick) ok.

Next Inspection: Stair treads

Approved: (Signed:)		Not approved – Hold Point: (Signed:) Peter to supply photos of installed treads	
Work may proceed: (Subject to completing above instructions)	Work may not proceed: (Further design/instruction and re-inspection required.)	Re-inspection required: (Following completion of above instructions.)	Contractor to supply photographs: (For approval following completion of above instructions. Work not to proceed until approval given.)

Note that the above approval does not include statutory inspections and approval which may be required by the Building Consent Authority. Similarly Building Consent Authority approval does not preclude re-inspection or implementation of further instructions directed herewith where the inspection was "Not Approved".

SITE INSPECTION REPORT

Job No.: 23020	Report No.: SR03	Seajay  CONSULTING ENGINEERS CIVIL • STRUCTURAL • FIRE 42 Michael Rd, PO Box 1713 Paraparaumu 5252 Phone: (04) 212 5150 • Cell: 021 121 4591 craig@seajay.co.nz
Date: 10/1/2025	Sheet 1 of 2	
Project: 200 Maungakotukutuku Road Paraparaumu		
Area Inspected: Stair Final		BC Number:
Inspected by: (Photos by Client)		Contractors Rep: Peter Saunders

Observations:

The client has installed 80mm thick plywood treads and landings as per the design drawings.




Photo 1 – Completed Stairs




Photo 2 – Completed stairs and treads




Photo 3 – Completed landing




Photo 4 – Typical tread installation

Instructions Given:

Nil

Next Inspection:

Approved: (Signed:) 		Not approved – Hold Point: (Signed:)			
Work <u>may</u> proceed: (Subject to completing above instructions)	☒	Work may <u>not</u> proceed. (Further design/instruction and re-inspection required.)	Re-inspection required (Following completion of above instructions.)	Contractor to <u>supply photographs</u> (For approval following completion of above instructions. Work not to proceed until approval given.)	

Note that the above approval does not include statutory inspections and approval which may be required by the Building Consent Authority. Similarly Building Consent Authority approval does not preclude re-inspection or implementation of further instructions directed herewith where the inspection was "Not Approved".

Disclaimer:

This document has been prepared solely for Peter Saunders name. The use of and reliance upon the information or opinions contained in this document by others without prior written consent from Seajay Consulting Engineers will be at such person's sole risk. Seajay Consulting Engineers accepts no responsibility or liability for the consequences of the unauthorised use of this document.

BC240320
Received by
Kapiti Coast District Council
10/01/25
via email



BC240320
Received by
Kapiti Coast District Council
10/01/25
via email



BC240320
Received by
Kapiti Coast District Council
10/01/25
via email



BC240320
Received by
Kapiti Coast District Council
10/01/25
via email







BC240320
Received by
Kapiti Coast District Council
05/12/2024
via Email



Statement of Compliance with the NZ Building Code

Consent No: 240320

ISSUED BY: **Kapiti Coast District Council**

PROJECT

Site Address: 198-200 Maungakotukutuku Road, Paraparau
Legal Description: LOT 20 DP 33688
Work Description: The project comprises construction of a new set of internal stairs in the existing two storey house.
Building Category: R1

OWNER

Name(s): Peter Saunders and Usani Saunders
Address: 200 Maungakotukutuku Road, Paraparaumu

-
- [P] Application for CCC received and accepted
 - [P] Consent description accurate and reflects amendments (if relevant).
 - [P] Confirm owner named on Building Consent application is current owner
 - [P] Confirm all required inspections completed and documented in GoGet
 - [P] If inspection(s) have been missed, have they been compensated for?
Engineer covering preline
 - [P] Work in accordance with approved consent and approved amendments
 - [P] Supporting documentation required in building consent addenda received
 - [P] Code Compliance Certificate Sign Off
 - [P] Approve to issue Code Compliance Certificate if all fees paid

NOTES:

Inspections Prepaid:
Inspections Done:

On review of the documentation and inspection notes it can be considered on reasonable grounds that all work has been completed in compliance with the building consent.

Signed:
Name: Stew Nelson
Position: Building Officer

Date: 10 March 2025

GoGet Inspection Audit Report

Consent No: **240320**
Applicant: **Seajay Consulting Engineers**
Site Address: **198-200 Maungakotukutuku Road, Paraparau**
Work Type: **The project comprises construction of a new set of internal stairs in the existing two storey house.**

Inspection Type: **Final Inspection**
Inspection Outcome: **Fail**
Inspected By: **Stew Nelson**
Inspection Date: **28 November 2024 9:26 a.m.**
Duration: **30 minutes**

Inspection Element	Status
Exterior	N/A
Interior	Fail
All previous inspections/notes passed	Fail
First inspection. Preline was noted on consent, SORG not required after reviewing documents but will require engineer PS4	
Drawings	Pass
On site and reviewed	
Additional information/plan	N/A
Service areas-floors/walls	N/A
Stair design	Pass
Assessed under Section 112	
1. Not uniform from top riser to landing as rest of stairs. Homeowner confirms old staircase was not uniform	
2. Slip resistance of LVL may or may not met building code requirements but SORG the performance is better than old treads. Observed old treads on site today	
Other riser and treads are fine	
Handrails	Pass
Inbuilt into barrier, 900mm	
Barriers from falling	Pass
>1m along stair, landing and second level	
Lighting	N/A
Laundering	N/A
Cooking facilities	N/A
Smoke detectors	Fail
Installed in dead space, both levels	
Food storage/preparation	N/A
Ventilation	N/A
HWC flues	N/A
HWC restraint	N/A
Tempering valve	N/A
Glazing - human impact	N/A
Window restrictors	N/A
Hot water temp	N/A
Solid fuel heater	N/A
Water supply tank	N/A
Trap seals and AAVS	N/A
Cistern flushing	N/A

WC pan connection	N/A
Non potable water signs	N/A
Septic system	N/A
Window labels	N/A
Non compliance discussed onsite	Pass
Photos to be provided, left email with homeowner. Please also provide photos of old staircase and written confirmation that old stairs were not uniform	
Final check complete	N/A
Other	N/A
Intertenancy/commercial	N/A
Other	N/A



Engineer covering
Taken at 9:12 AM on Thursday 28/11/2024



Taken at 9:12 AM on Thursday 28/11/2024



Taken at 9:13 AM on Thursday 28/11/2024



Handrail and barrier

Taken at 9:14 AM on Thursday 28/11/2024



Taken at 9:14 AM on Thursday 28/11/2024



Taken at 9:17 AM on Thursday 28/11/2024



Not uniform with rest of stairs
Taken at 9:17 AM on Thursday 28/11/2024



SD in deadspace
Taken at 9:17 AM on Thursday 28/11/2024



Old and new

Taken at 9:33 AM on Thursday 28/11/2024

SITE NOTICE

Consent No: **240320**
 Applicant: **Peter Saunders and Usani Saunders**
 Site Address: **198-200 Maungakotukutuku Road, Paraparau**
 Work Type: **The project comprises construction of a new set of internal stairs in the existing two storey house.**
 Building Category: **R1**

Inspection Type: **Final Inspection**
 Inspection Outcome: **Fail**
 Inspected By: **Stew Nelson**
 Inspection Date: **28 November 2024**

Failed Items

Interior

All previous inspections/notes passed

Smoke detectors

First inspection. Preline was noted on consent, SORG not required after reviewing documents but will require engineer PS4

Installed in dead space, both levels

Passed Items

Interior

Drawings

Stair design

On site and reviewed

Assessed under Section 112

1. Not uniform from top riser to landing as rest of stairs. Homeowner confirms old staircase was not uniform

2. Slip resistance of LVL may or may not met building code requirements but SORG the performance is better than old treads. Observed old treads on site today

Other riser and treads are fine

Inbuilt into barrier, 900mm

>1m along stair, landing and second level

Photos to be provided, left email with homeowner.

Please also provide photos of old staircase and written confirmation that old stairs were not uniform

GoGet Inspection Audit Report

Consent No: **240320**

Applicant: **Seajay Consulting Engineers**

Site Address: **198-200 Maungakotukutuku Road, Parapara**

Work Type: **The project comprises construction of a new set of internal stairs in the existing two storey house.**

Inspection Type: **Final Inspection**

Inspection Outcome: **Pass**

Inspected By: **Stew Nelson**

Inspection Date: **27 January 2025 3:23 p.m.**

Duration: **15 minutes**

Inspection Element	Status
Interior	Pass
All previous inspections/notes passed	Pass
PS4 received, SORG preline not required now	
Smoke detectors	Pass
Photos provided, SD's in compliant location	

SITE NOTICE

Consent No: **240320**
Applicant: **Peter Saunders and Usani Saunders**
Site Address: **198-200 Maungakotukutuku Road, Paraparau**
Work Type: **The project comprises construction of a new set of internal stairs in the existing two storey house.**
Building Category: **R1**

Inspection Type: **Final Inspection**
Inspection Outcome: **Pass**
Inspected By: **Stew Nelson**
Inspection Date: **27 January 2025**

Passed Items

Interior

All previous inspections/notes passed
Smoke detectors

PS4 received, SORG preline not required now
Photos provided, SD's in compliant location

KAPITI COAST DISTRICT COUNCIL

Consent No: 240320

Building Category: R1

Site Address: 198-200 Maungakotukutuku Road, Paraparau

Owner/Agent: Seajay Consulting Engineers

Inspections

The following inspections are required:

- 1 Preline Building
- 1 Final Inspection
- 2 Total Inspections

Residential Documentation

- 1 Application for CCC
- 1 Construction review PS4 statement for structural engineering